

Prepared for:
TOWN OF ADDISON




Water Master Plan

January 14, 2016

Prepared by:

BURY

5310 Harvest Hill Road
Suite 100/161
Dallas, TX 75230
972-991-0011





EXECUTIVE SUMMARY

1.0 Introduction

In May 2014, the Town of Addison authorized Bury, Inc. to perform a Water Master Plan Study. The goals of this project were to develop a robust steady-state and extended period water model, evaluate the integrity of the existing water distribution system, and craft a Capital Improvements Project Plan. Recommended improvement projects will serve as a foundation list for future design, construction, and financing of facilities required to meet Addison's water demands as a result of existing needs, 5-year-out projected growth, and build-out projected growth.

2.0 Distribution System Infrastructure

The Town of Addison water distribution system includes the following major system components:

- Pipelines, valves, and hydrants
- Six (6) Dallas Water Utilities (DWU) interconnections: two (2) primary delivery supply facilities and four (4) standby or emergency facilities
- Three (3) Carrollton emergency interconnections
- One (1) Farmers Branch emergency interconnection
- Surveyor Pump Station (4.0 MGD flow capacity) and Ground Storage Tank (2.0 MG storage capacity)
- Celestial Pump Station (20.0 MGD flow capacity) and Ground Storage Tank (6.0 MG storage capacity)
- Addison Circle Elevated Storage Tank (1.0 MG storage capacity)
- Surveyor Elevated Storage Tank (1.5 MG storage capacity)
- SCADA and Control Systems

The pipeline, valve, and hydrant components of the Town of Addison's water system were located by land survey and mapped using a combination of survey data, previous GIS data, and record drawings review.



3.0 Water Model Development

Bury developed a computer model of the Town of Addison water system by importing existing water system data into the water distribution system modeling software Bentley WaterGEMS V8i. The ModelBuilder tool within WaterGEMS was the means by which the building of the base physical infrastructure (i.e. pipes and junctions) of the water model was accomplished. The supply facilities, pump stations, and tanks (EST & GST) were manually added to the water model. Inputting operational settings for both initial conditions and extended period simulations was accomplished using the “controls” component in WaterGEMS to establish condition alternatives for the hydraulics present within the system.

Water demands were allocated to the water model based on user-type. A combination of Thiessen Polygons (from WaterGEMS) and GIS manipulation (spatial join) was used to develop a shapefile in GIS containing the water model junctions/nodes to which the corresponding demands were allocated. The allocated demands were then re-imported into WaterGEMS using the LoadBuilder tool and the demands were assigned to the corresponding junction in the water model. Average Daily Demand (ADD), Maximum Daily Demand (MDD), and Peak Hourly Demand (PHD) for Existing conditions, 5-year Period conditions, and Master Buildout conditions were developed and are summarized in Table ES-1.



Table ES-1 – Current and Projected Addison Water Demands

Year	ADD (MGD)	MDD (MGD)	PHD (MGD)
Existing (2015)	4.83	9.81	19.61
5-yr Period (2020)	5.16	10.47	20.95
Buildout	5.29	10.74	21.49

As a basis for the Extended Period Simulations (EPS), a Diurnal Demand Factor Pattern was generated and inputted into the water model. Chlorine residual data was obtained for the timeframe: January 2015 to September 2015 in order to effectively evaluate a correlation between water age and chlorine residual for the purposes of model evaluation. Development of the water age portion of the Water Model was to enhance the hydraulic model to obtain a nonspecific measure of overall water quality, evaluating storage tank turnover impacts on the distribution system’s water quality, and providing evaluation of the current flushing program.

4.0 Water Model Calibration & Validation

In order to more accurately represent and predict real-world conditions, calibration and validation of the water model was performed. Fire flow tests were conducted in the field and stand as the basis by which the water model was calibrated against real-world conditions. Scenarios and specific demand alternatives were set up in the water model using boundary conditions and water demands recorded in the field at the time of the fire flow tests. Minor adjustments were made to the water model such as changing Hazen-Williams C-values, pipe materials, and pipe connections until the model results were within a tolerable variance from the field test results. The calibration and validation process also included, because of some discrepancies between the recorded SCADA data and the provided pump curves, a number of iterations to obtain accurate pump curves that accurately represented the real-world functioning of the pumps. Multiple GST draw-down tests were conducted at each pump station to acquire real-world pump flow data with which to compare against the pump curves that had been



provided. Adjustments were made to the pump curve definitions in the water model to correct any discrepancies.

5.0 Hydraulic Analysis

Hydraulic analysis of the water distribution system included two (2) phases: Phase 1: Steady-State Analysis and Phase 2: Extended Period Simulations & Water Age Analysis. As the base for evaluating the hydraulic conditions of the water distribution system, design criteria for minimum & maximum allowable velocities, head-losses, pressures, and minimum fire flow rates were specified for normal steady-state (static) and fire flow demand scenarios. A summary of the hydraulic design criteria can be seen below.

Table ES-2 – Hydraulic Design Criteria

Hydraulic Criteria	Demand Condition	
	ADD, MDD, PHD	MDD + FF
Max Velocity (fps)	7	7
Max Head Loss (ft/ft)	4/1000 (or 0.004)	N/A
Min Pressure (psi)	40	25
Max Pressure (psi)	100	100
Min Specified Fire Flow (gpm)	N/A	1000

Steady-state model runs were conducted for twelve (12) demand alternatives by which the hydraulic design criteria were evaluated; the twelve (12) demand alternatives are a function/multiplication of the three (3) timeframes (Existing, 5-yr Period, and Buildout) and the four (4) demand conditions (ADD, MDD, PHD, and MDD+FF). The Steady-State Hydraulic Analysis represents a snapshot in time of the water distribution system in which the established initial conditions of the water model greatly influence what happens and what doesn't happen during a model run. Thus, careful caution was taken to establish accurate worst-case initial conditions. The steady-state model runs combined with requests from Addison were used to develop the initial CIP list.



TOWN OF ADDISON WATER MASTER PLAN

Among other things, the extended period simulations were used in Phase 2 of the water modeling to re-evaluate and refine the CIP plan. An additional two (2) CIP options were determined in order to meet hydraulic criteria. Also, the EPS model was used to evaluate the functional operational controls currently in use within the Town, analyze in greater depth the existing storage and pumping capabilities, and establish recommendations for emergency management by performing model runs for different, potential emergency scenarios.

The water age portion of the Water Model was used to enhance the hydraulic model so that water age analyses can provide a simple, nonspecific measure of overall water quality, evaluate storage tank turnover impacts on the distribution system's water quality, and provide evaluation of the current flushing program. Two (2) additional CIP options were determined during the analyses to reduce water age in certain portions of the system. Water age analyses were then combined with an evaluation of chlorine residual data for January – September 2015 to assist in developing a general picture of overall water quality within the system and to serve as the basis for the development of multiple recommendations to combat poor water quality.



6.0 Capital Improvement Projects (CIP) Plan

From the hydraulic analyses, a water infrastructure capital improvement projects (CIP) plan was developed to ensure hydraulic design criteria within the system are met so that Addison can continue to deliver great water distribution services. An initial list of CIP options was created by analyzing the ADD, MDD, PHD, and MDD + FF scenarios in the water model for existing, five-year (2020), and build-out conditions. Any areas or components that failed to meet specific design criteria were improved by a combination of line upsizing, replacing aging infrastructure, and adding new infrastructure. The list of CIP options was prioritized using risk-based analysis and can be seen in the table below.

Table ES-3 – CIP Risk, Cost, & Priority Summary

Option No.	Priority	Length (~ LF)	Option Description (including location)	CoF	LoF	Risk Factor	Improvement Cost Estimate (Current)
19	1	1499	Replacing 8-in CI with 8-in PVC Water Main (Greenhaven Village Shopping Ctr at Intersection of Marsh Ln & Spring Valley Rd)	3.04	2.60	7.90	\$566,622
18	2	583	Replacing 8-in DI with 8-in PVC Water Main (Prestonwood Place Shopping Ctr near Intersection of Beltline Rd & Montfort Dr)	2.91	2.54	7.40	\$264,449
16	3	4254	Upsizing 8-in CI to 10-in PVC Water Main (Running N to S from Beltline Rd to George H.W. Bush Elementary)	2.93	2.00	5.85	\$953,249
17	4	1617	Replacing 8-in CI with 8-in PVC Water Main (Intersection of Beltway Dr & Beltline Rd - Beltway Office Park)	2.53	2.00	5.05	\$611,226
6	5	1271	Upsizing 6-in CI to 8-in PVC Water Main (Lake Forest Drive)	1.60	3.10	4.96	\$460,278
10	6	1388	Upsizing 6-in Unk to 8-in PVC Water Main (Apartment Complex at NE Intersection of Addison Rd and Westgrove Dr)	1.95	2.22	4.33	\$516,264
24	7	116	Upsizing 16-in DI to 24-in RCCP (Intesection of Belt Line Rd and Quorum Dr)	2.43	1.44	3.49	\$292,290
23	8	1144	Upsizing 16-in RCCP to 24-in RCCP (in Belt Line Rd between Addison Rd and Quorum Dr)	2.43	1.26	3.06	\$845,736
3	9	101	Upsizing 8-in DI to 10-in PVC Water Main Near 36-in to 8-in Connection (SE Corner of Village on the Parkway)	1.25	1.44	1.80	\$69,569
7	10	1829	Upsizing 6-in PVC to 8-in PVC Water Main (Shadwood Apartments - Sydney Dr & Marsh Ln)	1.48	1.10	1.62	\$551,418
2	11	8	Upsizing Short Connection from 6-in to 8-in (North of Beltline on Quorum)	0.98	1.64	1.60	\$24,192
21	12	28	Upsizing 8-in PVC to 12-in PVC Water Main (The Wellington Square - Southern Edge of Addison)	1.43	1.10	1.57	\$26,531
14	13	144	Upsizing 8-in PVC to 10-in PVC Water Main (Quorum Office Building #2)	0.83	1.60	1.32	\$81,178



TOWN OF ADDISON WATER MASTER PLAN

11	14	168	Upsizing 8-in PVC to 12-in PVC Water Main (Excel Telecommunications Service Center to Addison Rd)	0.98	1.20	1.17	\$106,122
9	15	48	Upsizing 6-in Unk to 8-in PVC Water Main (Glenn Curtiss Dr & Addison Rd)	0.48	2.42	1.15	\$43,546
20	16	35	Upsizing 8-in Unk to 10-in PVC Water Main (The Madison - 15851 Dallas North Parkway)	0.60	1.82	1.09	\$22,050
13	17	30	Upsizing 6-in Unk to 8-in PVC Water Main (Quorum Office Building #2)	0.80	1.30	1.04	\$27,216
8	18	947	New 6-in PVC Water Main Loop (Talisker Apartments - off of Vitruvian Pkwy)	1.98	0.50	0.99	\$429,559
15	19	73	Upsizing 8-in PVC to 10-in PVC Water Main (Lateral off of Quorum Dr)	0.53	1.60	0.84	\$50,282
4	20	23	Upsizing 12-in PVC to 16-in DI Water Main Connection Between 36-in & 12-in Main (South of Beltline on Quorum)	0.78	0.90	0.70	\$25,734
25	21	149	New 8-in PVC Water Main Loop (Excel Telecommunications Service Center to Addison Rd)	0.55	1.00	0.55	\$238,341
22	22	20	Upsizing 8-in PVC to 12-in PVC Water Main (Millenium Phase I - NW Intersection of Arapaho & DNT)	0.75	0.70	0.53	\$18,950
26	23	93	New 8-in PVC Water Main Loop (FedEx Store - 4901 Airport Pkwy)	0.53	0.70	0.37	\$298,972
12	24	813	New 10-in PVC Water Main Loop (One Hanover Park Offices to Excel Pkwy along DNT)	0.48	0.70	0.33	\$341,460
5	25	210	Upsizing 6-in PVC to 8-in PVC Water Line for Lateral (Off of Claire Chennault Street)	0.25	1.00	0.25	\$105,840
1	26	3300	New 12-in PVC Water Main Loop (Apt. Complex in NW Corner of Town)	0.85	0.20	0.17	\$821,486

7.0 Conclusions and Recommendations

In conclusion, the recommendations and deliverables provided within this report are based upon sound engineering and modeling principles. However, while comprehensive, they are not all-inclusive of the many layers of intricacy present within Addison's water distribution system and at this point are at best a fair assessment and representation of the water infrastructure assets at this time. Even though Addison's distribution system is robust and the mapping, water model, capital improvement projects plan, and water master plan report provide a comprehensive evaluation of the system, there is always room for continual improvement. Wrapped up within these future considerations is the recommendation that the Water Master Plan report developed herein be updated regularly (recommended annually at a minimum) to accommodate for any changes, variations, or new infrastructure development made to the water distribution system.



Table of Contents

1.0 INTRODUCTION14

1.1 GENERAL..... 14

1.2 OBJECTIVES/SCOPE OF WORK..... 14

2.0 DISTRIBUTION SYSTEM INFRASTRUCTURE15

2.1 PIPELINES, VALVES, AND HYDRANTS 17

2.2 SUPPLY FACILITIES 18

 2.2.1 DWU Interconnections 19

 2.2.1.1 Primary Delivery Facilities..... 19

 2.2.1.2 Standby Delivery Facilities 19

 2.2.2 Carrollton Interconnections 20

 2.2.3 Farmers Branch Interconnections 20

2.3 SURVEYOR PUMP STATION AND GROUND STORAGE TANK..... 20

2.4 CELESTIAL PUMP STATION AND GROUND STORAGE TANK 21

2.5 ADDISON CIRCLE ELEVATED STORAGE TANK 22

2.6 SURVEYOR ELEVATED STORAGE TANK 22

2.7 SCADA AND CONTROL SYSTEMS 22

3.0 WATER MODEL DEVELOPMENT.....23

3.1 MODEL SETUP AND ASSUMPTIONS..... 23

 3.1.1 Physical Component Development 23

 3.1.1.1 Pipes, Junctions, and Skeletonization 24

 3.1.1.2 Supply Facilities (Reservoirs) 25

 3.1.1.3 Tanks (EST & GST) 26

 3.1.1.4 Pump Stations 26

 3.1.2 System Operational Settings..... 27

3.2 WATER SYSTEM DEMANDS..... 28

 3.2.1 Existing Water Demand Development (Historical) 28

 3.2.1.1 ADD Development - Meter Records 28

 3.2.1.2 MDD Development - Pump Station Flow Data 30

 3.2.1.3 MinDD Development - Pump Station Flow Data 31

 3.2.1.4 Peaking Factors & PHD Development..... 31



3.2.2 Allocation Process 33

3.2.3 Diurnal Demand Pattern 35

3.2.4 Population & Land Use..... 37

3.2.5 Future Water Demand Development..... 39

3.3 WATER AGE INFORMATION 41

4.0 WATER MODEL CALIBRATION AND VALIDATION.....41

4.1 FIRE FLOW TESTS 41

 4.1.1 Locations & Maps 42

 4.1.2 Data Collected..... 44

 4.1.3 Results..... 44

4.2 PUMP CURVE EVALUATIONS 45

4.3 ITERATIVE CALIBRATION PROCESS 45

5.0 HYDRAULIC ANALYSIS46

5.1 DESIGN CRITERIA 47

5.2 PHASE 1: STEADY-STATE HYDRAULICS 48

5.3 PHASE 2: EXTENDED PERIOD SIMULATIONS 50

 5.3.1 Calibration & Validation 51

 5.3.2 Steady-State CIP Plan Evaluation..... 51

 5.3.3 Operational Controls Evaluation..... 52

 5.3.4 Storage and Pumping Evaluation 53

 5.3.5 Emergency Management Evaluation..... 56

5.4 PHASE 2: WATER AGE & QUALITY ANALYSIS..... 58

 5.4.1 General System Water Quality 58

 5.4.2 Water Quality Improvement Recommendations..... 59

6.0 CAPITAL IMPROVEMENT PROJECTS (CIP) PLAN62

6.1 COST ESTIMATES..... 65

6.2 RISK-BASED ANALYSIS 66

6.3 IMPACT FEE ANALYSIS 70

7.0 CONCLUSION AND FUTURE CONSIDERATIONS72

APPENDICES73



List of Figures

Figure 2.1 – Existing Water System	16
Figure 3.1 – User-Type Map.....	34
Figure 3.2 – Diurnal Demand Pattern	36
Figure 3.3 – Future Development Map.....	40
Figure 4.1 – Fire Flow Test Locations.....	43
Figure 5.1 – MinDD Water Age Map – Before CIP	60
Figure 5.2 – MinDD Water Age Map – After CIP.....	61
Figure 6.1 – Capital Improvement Projects Plan Map	64
Figure 6.2 – Risk-Based Analysis Graphical Depiction	70



List of Tables

Table 2.1 – Statistical Breakdown of Town of Addison Pipelines.....	18
Table 2.2 – Surveyor Pump Station Data	21
Table 2.3 – Celestial Pump Station Data.....	22
Table 3.1 – Tank Physical & Operating Range Attributes	26
Table 3.2 – Pumping Facilities Summary	27
Table 3.3 – Demand User-Types	30
Table 3.4 – Existing ADD, MDD, Peaking Factor, and PHD Summary	32
Table 3.5 – Existing ADD, MDD, Peaking Factor, and PHD Summary	38
Table 3.6 – Existing ADD, MDD, Peaking Factor, and PHD Summary	39
Table 4.1 – Fire Flow Test Data.....	44
Table 5.1 – Hydraulic Design Criteria.....	47
Table 5.2 – Statistical Summary of Steady-State – CIP Identified	49
Table 5.3 – Statistical Summary of Extended Period Simulation – CIP Identified	51
Table 5.4 – Operational Control Settings Summary	53
Table 5.5 – TCEQ Storage Tank Capacity Requirements.....	53
Table 5.6 – Existing Storage Tank Analysis	54
Table 5.7 – TCEQ Pumping Capacity Requirements	54
Table 5.8 – Existing Pumping Capacity Analysis	55
Table 5.9 – Emergency Management Scenarios.....	57
Table 6.1 – Identified Capital Improvement Projects (CIP)	63
Table 6.2 – Estimated Water System Construction Unit Prices.....	65
Table 6.3 – Consequence of Failure (CoF) Criteria Weightings	67
Table 6.4 – Likelihood of Failure (LoF) Criteria Weightings	67
Table 6.5 – Likelihood of Failure Sub-Criteria for Rating Pipe Material Example.....	67
Table 6.6 – CIP Risk, Cost, & Priority Summary	69
Table 6.7 – Impact Fee Comparison Summary	71



List of Appendices

Appendix A – Emergency Interconnection Record Drawings

Appendix B – Pump Station Layouts

Appendix C – Pump Curves

Appendix D – Detailed Fire Flow Test Location Maps

Appendix E – Proposed Operational Control Setting Parameters

Appendix F – Chlorine Residuals (Jan. - Sept. 2015)

Appendix G – CIP Plan Priority Matrix

Appendix H – Risk Based Analysis Calculations & Data

Appendix I – Proposed Impact Fee Schedule

Appendix J – Impact Fee Analysis Calculations & Data



Abbreviations

ADD – Average Daily Demand

CI – Cast Iron

CoF – Consequence of Failure

DI – Ductile Iron

DWU – Dallas Water Utilities

EPS – Extended Period Simulation

GPD – Gallons per Day

GPM – Gallons per Minute

HGL – Hydraulic Grade Line

LoF – Likelihood of Failure

MDD – Maximum Daily Demand

MGD – Million-Gallons per Day

MinDD – Minimum Daily Demand

NCTCOG – North Central Texas Council of Government

PCCP – Pre-Stressed Concrete Cylinder Pipe

PHD – Peak Hourly Demand

PRVs – Pressure Reducing Valves

PS – Pump Station

PVC – Poly-Vinyl Chloride

ROW – Right-of-Way

SCADA – Supervisory Control and Data Acquisition

TDH – Total Dynamic Head

Unk – Unknown

WAA – Water-Age Analysis



1.0 INTRODUCTION

1.1 General

In May 2014, the Town of Addison authorized BURY, Inc. to perform a Water Master Plan Study. The goals of this project were to 1.) Develop a robust steady-state and extended period simulation water model, 2.) Evaluate the integrity of the existing water distribution system, and to 3.) Craft a Capital Improvements Plan by prioritizing infrastructure projects based on their timeline of development, critical nature, and the Town of Addison's immediate needs. Recommended improvement projects will serve as a foundation list for future design, construction, and financing of facilities required to meet Addison's water demands as a result of existing needs, 5-year out projected growth, and build-out projected growth.

1.2 Objectives/Scope of Work

The scope of work for this Water Master Plan Study includes the following objectives:

- Water Model Development
- Field Testing and Water Model Calibration
- Water Modeling Phase 1: Steady State Hydraulic Analyses of Average Day Demand (ADD), Maximum Day Demand (MDD), Peak Hour Demand (PHD), and Maximum Day Demand plus Fire Flow (MDD + FF) for three timeframe conditions:
 - Existing System Conditions
 - 5-yr Period System Conditions
 - Master Build-Out System Conditions
- Water Modeling Phase 2: Extended Period Simulations to evaluate the following:
 - Steady-State CIP Plan
 - System Operational Controls
 - Storage and Pumping Capacities
 - Emergency Management Scenarios



- Water Modeling Phase 2: Water Age Analyses to evaluate/provide the following:
 - General System Water Quality
 - Water Quality Improvement Recommendations
- Develop Capital Improvement Project Plan by identifying, recommending and prioritizing projects needed to meet hydraulic design criteria and incorporating the Town of Addison's existing troublesome maintenance locations

2.0 DISTRIBUTION SYSTEM INFRASTRUCTURE

The Town of Addison operates their water system within one pressure plane. Infrastructure in a water distribution system generally consist of pipelines, valves, hydrants, pump stations, ground storage tanks (GST), elevated storage tanks (EST), and normally water treatment facilities. However, the Town of Addison has no water treatment facilities because they buy wholesale treated water from DWU. The wholesale treated water is delivered to the Town of Addison at two locations: Surveyor Pump Station and Celestial Pump Station. As important as it is to understand the system infrastructure and it's interconnected functioning for the purpose of physical operation and maintenance it is just as critical for water modeling because a water model is only as good as the base physical components it is built upon. Thus, as a means of elucidation this section of the report will discuss the existing infrastructure and the process undertaken to gather, collect, develop, and compile physical infrastructure data into maps and databases for the ultimate purpose of building the water model which will be discussed in the following section. See **Figure 2.1** for an overall layout map of Addison's existing distribution system infrastructure.




Figure 2.1

**Town of Addison
Existing Water System**





2.1 Pipelines, Valves, and Hydrants

The ability to effectively model a water system depends largely on the accuracy of the base physical infrastructure data used to perform the initial build of the model. For increased accuracy, land surveying was used to pick up the geographic locations and ground elevations of valves and hydrants. Next, the piping was mapped using a combination of survey data, previous GIS data, and record drawings review. The prior GIS data was used as the initial approximation of the location and physical attributes of the infrastructure. The land survey data acquired in conjunction with a record drawing review was used to accurately improve, update, and map the existing infrastructure using a connect-the-dot approach between valves and hydrants, particularly focusing on the pipe lines themselves to ensure proper sizing, connectivity, material, and age of pipe. The attribute table for the water lines was populated with detailed information acquired largely from the record drawings themselves, such as installation year, record drawing name, owner, and physical features such as size, material, and etc. The elevation data acquired by the land survey for the valves and hydrants themselves was used later during the calibration process to evaluate hydraulic grade lines for the purpose of comparing against the model. The ground elevations within the city range from 496 feet to 686 feet.

Addison pipeline infrastructure is significant, consisting of over 100 miles of pipe ranging in size from 42-inch diameter mains to 3/4-inch diameter service lines. The list of pipeline materials present in Addison includes: copper (CU), ductile iron (DI), cast iron (CI), reinforced concrete cylinder pipe (RCCP), pre-stressed concrete cylinder pipe (PCCP), Steel, and poly-vinyl chloride pipe (PVC). See **Table 2.1** below for a statistical breakdown of the Town of Addison's pipelines.



Table 2.1 – Statistical Breakdown of Town of Addison Pipelines

Pipeline Material	Approximate Length (Linear Feet)	Percentage of Total Length
CU	20,031	3.5%
DI	30,217	5.7%
CI	34,769	6.5%
PCCP & RCCP	22,869	4.3%
Steel (at Celestial PS)	185	< 1.0%
PVC	289,480	54.2%
Unknown (Unk)	136,091	25.5%

Also, present within Addison is DWU owned infrastructure including approximately 7 miles of pipeline ranging in size from 6 inches to 84 inches and the Beltwood Reservoir Facility which is slightly northwest of the Addison Rd and Belt Line Rd intersection. Clear distinction of Addison owned versus DWU owned infrastructure has been made and can be seen in **Figure 2.1: Existing Water System**. The water model developed included only Addison owned infrastructure.

2.2 Supply Facilities

Just as critical as the proper physical data of the pipelines, valves, and hydrants is the proper physical data of the supply connections present within Addison. Supply interconnections discussed in this section include DWU, Carrollton, and Farmers Branch and both wholesale supply facilities and emergency facilities. Addison has a total of six (6) connection locations with DWU: two (2) primary delivery supply facilities and four (4) standby (emergency) facilities. Addison, also, has three (3) emergency interconnections with Carrollton and one (1) with Farmers Branch. The main intent of the emergency interconnections is to provide supply either to Addison from DWU, to Addison from DWU through Carrollton or Farmers Branch, or to Carrollton and Farmers Branch from DWU through Addison in the case of an emergency or pump station failure. The



two (2) primary delivery facilities operate as the main, normal operation supply connections for the Town of Addison. Please see **Figure 2.1** for a map detailing the supply facility locations.

2.2.1 DWU Interconnections

Addison purchases wholesale treated water from DWU at a contractual rate of 11.0 MGD, of which 9.8 MGD is delivered through the Celestial Pump Station connection and 1.2 MGD is delivered through the Surveyor Pump Station connection. These two (2) interconnections constitute the primary delivery facilities for DWU to Addison. As mentioned above, there are also four (4) standby (emergency) connection locations between Addison and DWU which, per the wholesale treated water contract with Dallas, are referred to as standby delivery facilities.

2.2.1.1 Primary Delivery Facilities

The Surveyor and Celestial Rate of Flow Controlled (ROFC) metering stations were installed and placed into operation in 1976 and 1988, respectively. They have a maximum combined delivery flow capacity of 24.0 MGD. The Surveyor Rate of Flow Controlled (ROFC) metering station is located at 15130 Surveyor Blvd. and is equipped with a 12" venturi meter capable of delivering 4.0 MGD. The Celestial ROFC metering station is located at 5510 Celestial Rd. and is equipped with a 20" venturi meter capable of delivering 20.0 MGD. Although the ROFC metering stations are sized for up to 24.0 MGD, the current wholesale contract with DWU is capped at 11.0 MGD. The two (2) primary delivery connection meter vaults are owned by DWU.

2.2.1.2 Standby Delivery Facilities

Standby Delivery Facilities serve as emergency supply connections and thus act as integral components of a robust water infrastructure system. The four (4) standby delivery facilities have a maximum combined delivery flow capability of approximately 18.9 MGD. The first standby delivery facility consists of an 8" FM (fire service) meter with a maximum delivery capability of 4.0 MGD and is located at the northeast corner of Addison Road and Belt Line Road. The second standby delivery facility consists of a 6" FM (fire service) meter with a maximum delivery capability of 2.3 MGD and is located at the southeast corner of Dallas Parkway and Westgrove



Road. The third standby delivery facility consists of a 10” Turbine meter with a maximum delivery capability of 6.3 MGD and is located in the Celestial Road ROW directly north of the Celestial PS. The final standby delivery facility consists of a 10” Turbine meter with a maximum delivery capability of 6.3 MGD and is located slightly east of the southeast corner of Dallas Parkway and Belt Line Road. See **Figure 2.1** for a map of the Standby Delivery Facility locations. Also, see **Appendix A** for copies of the record drawings for each Standby Delivery Facility.

2.2.2 Carrollton Interconnections

As mentioned above, there are three (3) interconnections with Carrollton that serve as an alternate emergency connections. Each interconnection is bi-directional which allows emergency water supply for either the Town of Addison or the City of Carrollton. Based on record drawing review and discussions with operations staff the location of the three (3) interconnection facilities have been identified to be 1) slightly north of the Surveyor Blvd and Lindbergh Dr intersection, 2) at the NE corner of the Wiley Post Rd and Midway Rd intersection, and 3) on the SE corner of the Midway Rd and Kellway Circle intersection. See **Figure 2.1** for a map of the Carrollton Interconnection locations.

2.2.3 Farmers Branch Interconnections

There is one (1) interconnection with Farmers Branch that serves as an alternate emergency connection which is, also, bi-directional. Once again, based on record drawing review and discussions with operations staff the location of the Farmers Branch connection has been identified to be on Beltwood Pkwy E a bit south of Belt Line Rd on the west side of Beltwood Pkwy E. on the edge of the Addison and Farmers Branch City boundary.

2.3 Surveyor Pump Station and Ground Storage Tank

The Surveyor Pump Station and Ground Storage Tank function as a single facility consisting of three (3) centrifugal booster pumps and a 2.0 MG Ground Storage Tank. The facility was formally constructed and put into operation in 1976. The Ground Storage Tank is a 26 foot tall concrete



tank with a diameter of 120 feet. The inflow pipe into the tank is a 12-inch diameter line and the overflow pipe diameter is 12-inches. The outflow pipes feeding into the pump station are two (2) 24-inch diameter lines. The three (3) pumps in the pump station consist of two (2) different pump curves. See **Table 2.2** below for a breakdown of the pumps. The pumps act in parallel and have a total capacity of approximately 9850 GPM and a firm capacity of 6000 GPM. The total capacity is the summation of all of the pumps operating point capacities, and the firm capacity is the total capacity minus the largest pump. More detail regarding the operational criteria of the Surveyor Pump Station will be discussed in the proceeding sections. See **Appendix B** depicting the Surveyor & Celestial Pump Station layouts.

Table 2.2 – Surveyor Pump Station Data

Pump #	Pump Flow (gpm)	TDH (feet)	Impeller
1	3850	197	17"
2	3000	175	14.5"
3	3000	175	14.5"
Total Capacity (gpm):	9850*		
Firm Capacity (gpm):	6000**		

* Total Capacity = Summation of all of the pumps operating point capacities

** Firm capacity = total capacity minus the largest pump

2.4 Celestial Pump Station and Ground Storage Tank

The Celestial Pump Station and Ground Storage Tank function as a single facility consisting of five (5) two-stage vertical turbine booster pumps and a 6.0 MG Ground Storage Tank. The facility was formally constructed and put into operation in 1988. The Ground Storage Tank is a 26 foot tall concrete tank with a diameter of 206 feet. The inflow pipe into the tank is a 36-inch diameter line and the overflow pipe are (2) – 24-inch diameter lines. The outflow pipes feeding into the pump station are two (2) 42-inch diameter lines. The five (5) pumps in the pump station consist of three (3) different pump curves. See **Table 2.3** below for a breakdown of the pumps. The pumps act in parallel and have a total capacity of approximately 26,200 GPM and a firm capacity of 19,200 GPM. The total capacity is the summation of all of the pumps operating point capacities, and the firm capacity is the total capacity minus the largest pump. More detail



regarding the operational criteria of the Celestial Pump Station will be discussed in the proceeding sections. See **Appendix B** depicting the Surveyor & Celestial Pump Station layouts.

Table 2.3 – Celestial Pump Station Data

Pump #	Pump Flow (gpm)	TDH (feet)	Impeller
1	7000	190	18.70"
2	3200	190	12.95
3	7000	190	18.70"
4	2000	190	10.78"
5	7000	190	18.70"
Total Capacity (gpm):	26,200*		
Firm Capacity (gpm):	19,200**		

* Total Capacity = Summation of all of the pumps operating point capacities

** Firm capacity = total capacity minus the largest pump

2.5 Addison Circle Elevated Storage Tank

The Addison Circle Elevated Storage Tank is an iconic part of the Town of Addison’s water infrastructure system. The EST was built and put into operation in 1977. The tank has a 1.0 MG capacity and is 150 feet tall with a diameter of 74 feet. The inlet/outlet pipe size is 24-inches, and the overflow pipe diameter is 12-inches. More detail regarding the operational criteria of the Addison Circle EST will be discussed in the proceeding sections.

2.6 Surveyor Elevated Storage Tank

The newest addition to the Addison water distribution system was built and put into operation in 2013. The tank has a 1.5 MG capacity and is approximately 177 feet tall with a maximum diameter of 90 feet. The inlet/outlet pipe size is 24-inches, and the overflow pipe diameter is 16-inches. More detail regarding the operational criteria of the Surveyor EST will be discussed in the proceeding sections.

2.7 SCADA and Control Systems

A key to any well-functioning water distribution system is an effective SCADA and Control System. Proper understanding of the SCADA system and more particularly the varied operational Control



Systems present within the Town is key to developing an accurate water model. All of the primary supply facilities within Addison have sensors for operation and control at each facility. Refer to the Town of Addison [Public Works, Utilities Division Operations Manual](#) for details of the SCADA system operations and controller information.

3.0 WATER MODEL DEVELOPMENT

This section will discuss the steps and efforts taken to develop and build the Water Model. Subsections to be included herein include Physical Component Development, System Operational Criteria Inputting, Population (discussing and developing correlations between population and demand), and Water System Demand development.

3.1 Model Setup and Assumptions

The software used by the team for water modeling was Bentley WaterGEMS V8i which has a number of dynamic features, tools, and capabilities. The initial model setup included the created GIS map data, infrastructure data, and operational criteria. Once created the initial model was reviewed to verify that the data was inputted/inserted correctly and that the data inputted/inserted made sense in comparison to real-world conditions. The subsections discussed herein are essentially presented in order by which they were developed in the model.

3.1.1 Physical Component Development

Included in this section is a summation of the steps used to import and input the physical infrastructure data: pipes, junctions, supply facilities, pump stations, and tanks (EST & GST) which were acquired and mapped as discussed in **Section 2.0 Distribution System Infrastructure**. The ModelBuilder tool within WaterGEMS was the means by which the building of the base physical infrastructure (i.e. pipes and junctions) of the water model was accomplished. The supply facilities, pump stations, and tanks (EST & GST) were manually added to the water model.



3.1.1.1 Pipes, Junctions, and Skeletonization

The first step of creating the water model was an initial build (i.e. importation) of the GIS Addison Waterline shapefile data using the ModelBuilder tool. Upon the initial build of the model, pipe connections (junctions) were automatically generated at all pipe endpoints using spatial relationships between the pipelines. Next, the process of skeletonizing the model, trimming out the less critical pipes and junctions, was used to simplify the model. The general assumption made was that pipes 6-inches in diameter or smaller were the least critical unless they functioned as a critical connectivity or loop within the system in which case they were maintained. Thus, all pipes and associated junctions 6-inches in diameter or smaller that did not play a critical role in the connectivity of the water model were removed from the model. The Skeletonization process helped greatly in simplifying the model. Then, once the model was skeletonized, a detailed, iterative review, refinement, and clean-up process was conducted to ensure the pipelines and junctions accurately reflect real-world connectivity of the infrastructure. Upon completion of the connectivity review and refinement, the junctions were exported to a Shapefile in order to assign elevations by using AutoCAD Civil 3D to project the junction points to the NCTCOG surface acquired from Addison. Elevations of the junctions in the water model are crucial to mimic accurately the hydraulic conditions of the real world. Once the junctions were assigned elevations, the junction nodes were then reimported into the Water Model along with the skeletonized water model using the ModelBuilder tool. At this point, the building of the base physical components of the water model were completed and relatively finalized. However, it should be noted that while progressing forward with the model development process, further gaps and holes in the physical structure of the model were discovered and corrected in kind. For instance, after many other components were added to the Water Model it was discovered that there were some connectivity missing between some of the pipes within the model and that there were also three (3) pressure reducing valves (PRVs) missing, as well. Essentially, it is upon this physical component base that the supply facilities, pump stations, tanks, system operational controls, and demand allocation water model components were built.



3.1.1.2 Supply Facilities (Reservoirs)

In the case of this Water Model, the definition to be used for supply facilities will be the supply connections with the surrounding cities and it will be represented in the model as a reservoir with a physical elevation set to the hydraulic grade line present in the respective water system at that connection point. As discussed previously in **Section 2.2 Supply Facilities**, there are two (2) primary delivery facilities which act as the water supply connections for the Water Model, and there are an additional eight (8) standby delivery facilities, four (4) with DWU, three (3) with Carrollton, and one (1) with Farmers Branch that have been included/added to the Water Model to allow for modeling and analysis of emergency scenarios within the model. It should be noted that at this time, in accord with the scope of work of this project, no hydraulic data regarding the Carrollton and Farmers Branch connections has been acquired and there is no way of accurately incorporating them into any modeling scenarios; however, if hydraulic data is ever collected it would be simple to input into the model and run analysis of the effects. The two (2) DWU primary and four (4) DWU standby delivery facilities are located within DWU's North High Pressure Plane which has an established hydraulic grade line (HGL) of 751.5 feet based on the overflow height of the elevated storage tanks present within this DWU pressure plane. Thus, an elevation of 751.5 feet was assigned to all six (6) DWU delivery facilities. In the Water Model, DWU facilities (reservoir components) were connected to the respective ground storage tanks and subsequently pump stations for the two (2) primary delivery facilities and via connections to metering vaults represented by isolation valves for the eight (8) standby delivery facilities. From a water model perspective, the supply facility (reservoir) acts as a constant, steady supply of water feeding the system; whereas, the tanks fluctuate in junction with the pumps in a corollary fashion to mimic real-world hydraulic grade line conditions.



3.1.1.3 Tanks (EST & GST)

As discussed previously in **Section 2.2 Supply Facilities**, there are four (4) tanks within the Town of Addison’s water distribution system. There are two (2) GSTs, each located at a Pump Station site: Surveyor GST and Celestial GST. There are, also, two (2) ESTs: Addison Circle EST and Surveyor EST. These tank components were added and connected to the system using the tank feature in WaterGEMS, and the physical data of the tanks was set to match the information discussed in Section 2.2. Operation related physical inputs were added to the tanks such as initial water levels/elevations, low-water level/elevation alarms, maximum elevations, and high-water level/elevation alarms were set. These physical inputs become critical when performing Extended Period Simulation (EPS) model runs. See **Table 3.1** below for a summary of the physical inputs for each tank.

Table 3.1 – Tank Physical & Operating Range Attributes

Tank Name	Ground Elev. (ft)	Operating Range Type	Elev. (Base) (ft)	Elev./Level (Minimum) (ft)	Elev./Level (Initial) (ft)	Elev./Level (Maximum) (ft)	Elev./Level (Low Alarm) (ft)	Elev./Level (High Alarm) (ft)	Vol. Full (Input) (MG)	Dia. (ft)	Install Year
Surveyor GST	603	Level	600	7.5	15	24.92	7.5	23	2	120	1976
Celestial GST	594	Level	574.42	12	17	24	12	23.5	6	206	1988
Surveyor EST	598.7	Elevation	735.1	735.1	751.5	775.7	751.1	773.1	1.5	90	2011
Addison Circle EST	639	Elevation	735.25	735.25	753.5	775.25	753.25	773.25	1	74	1977

3.1.1.4 Pump Stations

The two (booster) pump stations owned and operated by the Town of Addison are the Surveyor PS and Celestial PS. Description of the physical nature of these two (2) pump stations and the pumps present within them was discussed in **Section 2.3** and **2.4**. See below in **Table 3.2** a summary of the pumps operating points. See **Appendix C** for a copy of each pump curve. Unfortunately, the process of acquiring the correct pump curves for each pump was a bit more tedious than originally anticipated; an iterative process to obtain the correct, real-world pump curves was conducted and is discussed in **Section 4.2 Pump Curve Evaluations**.



Table 3.2 – Pumping Facilities Summary

Pump	Capacity (gpm)	TDH (ft)
Celestial Pump 1	7,000	190
Celestial Pump 2	3,200	190
Celestial Pump 3	7,000	190
Celestial Pump 4	2,000	190
Celestial Pump 5	7,000	190
Surveyor Pump 1	3,850	197
Surveyor Pump 2	3,000	175
Surveyor Pump 3	3,000	175

The pumps were added to the Water Model using the pump and pump station features in WaterGEMS and connected up to the appropriate pipes in the base model. The pump curve data was inputted using the “multiple point” pump definition and then they were assigned to the appropriate pump. Operational control criteria were then acquired and established for each pump which is further discussed in the next section.

3.1.2 System Operational Settings

Included in this section is a quick discussion on the initial conditions and a brief summary of the system operational settings used in the model. The operational settings were developed in accord with the Town of Addison’s Public Works, Utilities Division Operations Manual and have been established to mimic Operational Settings A from the manual which have been updated to match the new system conditions including Surveyor Elevated Storage Tank.

During the first phase of the water modeling, steady-state hydraulic analyses were conducted in which initial conditions became critical because each run was simply a snapshot in time, and thus, the results depended greatly on which pumps were on or off and what the Elevated Storage Tank levels were. Throughout the steady-state hydraulic analyses, initial conditions were established to mimic the likely real-world worst-case conditions which vary depending on the water demand scenario. The initial condition variations were determined based upon established trends within the Town of Addison, discussion with Town staff regarding general operational norms for



particular times of the year, and general adherence to the Operational Settings A detailed in the Operations manual.

During the second phase of the water modeling, extended period simulations were conducted in which functioning Operational Settings became necessary to accommodate changes in the operations of the system over time. For instance, the response of tank levels, pumps on/off, and general reactionary relationship between all of the components system is one aspect being analyzed during the extended period simulations. Inputting operational settings was accomplished using the “controls” component in WaterGEMS to establish condition alternatives in relation to the hydraulic conditions present within the system. Refer to **Section 5.3.3** for a discussion on the proposed Operational Controls developed using the model.

3.2 Water System Demands

Accurate depiction of water system demands is critical to effectively modeling a water distribution system. The scope of Phase 1 of the water modeling (Steady-State) included the development of Average Daily Demand (ADD), Maximum Daily Demand (MDD), and Peak Hourly Demand (PHD) for Current/Existing conditions, 5-year period conditions, and Master-Buildout conditions. The scope of Phase 2 of the water modeling (Extended Period Simulation) included the development of a diurnal demand pattern. The development, calculation, and allocation of the aforementioned demand conditions will be discussed within this section.

3.2.1 Existing Water Demand Development (Historical)

3.2.1.1 ADD Development - Meter Records

The basis for the development of the existing ADD was the historical customer metered (monthly) demand records for the years 2012, 2013, and 2014. These meter records were acquired from Addison via the water billings department. Initial evaluation of the metered demand records yielded discovery of a variety of discrepancies which required Data Trimming (data cleanup).



Upon completion of the Data Trimming, ADDs were calculated by User Type per meter. Further discussion of these two efforts will be discussed within this subsection.

3.2.1.1.1 Data Trimming

The 2012, 2013, and 2014 historical customer metered (monthly) demand records were provided as raw tabular data in the form of an excel table for each year that, when analyzed in more detail, yielded discovery of a variety of discrepancies such as more/less values of data than the number of months in a year, numerous demand records having a value of zero, and multiple records per meter/customer. Due to these discrepancies in the demand records, the accuracy of the data for the purpose of calculating existing ADD was considered suspect. Thus, a thorough review of the data was conducted and the invalid, inconsistent, and discrepant records were corrected or deleted altogether if they were discovered to be wrong. This process of Data Trimming was fairly tedious and time-consuming, but it was necessary for assuring the accuracy of the data from which the existing ADDs were calculated.

3.2.1.1.2 Demand Calculations

How the demands were to be allocated in the Water Model dictated the form and method by which demands were calculated. It was assumed that demand records for the years 2012-2014 would be a fairly representative time period for reflecting the existing demands for the year 2015. In excel, each year's records were sorted, filtered, and organized based first upon user-type, then by customer address, and then by meter. The user-types were provided in the historical customer metered (monthly) demand records and are as seen below.



Table 3.3 – Demand User-Types

User-Type	Description
COMLG	Commercial Large
COMSM	Commercial Small
H_M	Hotel & Motel
INDLG	Industrial Large
INDSM	Industrial Small
IRRLG	Irrigation Large
IRRSM	Irrigation Small
MFLG	Multi-Family Large
MFSM	Multi-Family Small
SCH	School
SF	Single Family
TOWN-WA*	Town Owned Facilities
TOWN-IR*	Town Irrigation (Parks, Medians, Public Spaces, etc.)

*The UserType provided by Addison was actually just TOWN, but it was delineated into TOWN-WA and TOWN-IR by adding the UTILITYTYPE filter of WA (general water) and IR (irrigation water)

Once the data was properly sorted, calculations were performed for each year (2012, 2013, and 2014) to generate Town-Wide ADDs and user-type per meter specific ADDs which were then subsequently averaged and summarized to attain the existing (2015) ADDs. The following sections discuss how the existing MDDs were developed, how peaking factors were calculated, and how the peaking factors were used to calculate the MDD and PHD for each user-type per meter.

3.2.1.2 MDD Development - Pump Station Flow Data

In order to calculate ADD to MDD peaking factors (equal to MDD divided by ADD), baseline MDDs needed to be developed for each year. The calculation of a MDD for each year was accomplished through the analysis of the 2012, 2013, and 2014 “Town of Addison Daily Pump Station Daily Activity CP” records for the Celestial PS and Surveyor PS. Just as with the ADD, it was assumed that the analysis of pump station discharge records 2012-2014 suffices as a representative reflection of existing (2015) MDDs. The data was entered into excel, analyzed, and summarized to calculate the Town-Wide MDD per year in million-gallons per day (MGD).



3.2.1.3 MinDD Development - Pump Station Flow Data

For the purpose of evaluating Water Age, Minimum Daily Demands (MinDD) were calculated. In order to calculate ADD to MinDD peaking factors (equal to MinDD divided by ADD), baseline MinDDs needed to be developed for each year. The calculation of a MinDD for each year was accomplished through the analysis of the 2012, 2013, and 2014 “Town of Addison Daily Pump Station Daily Activity CP” records for the Celestial PS and Surveyor PS. Just as with the ADD, it was assumed that the analysis of pump station discharge records 2012-2014 suffices as a representative reflection of existing (2015) MinDDs. The data was entered into excel, analyzed, and summarized to calculate the Town-Wide MinDD per year in million-gallons per day (MGD).

3.2.1.4 Peaking Factors & PHD Development

At this point, progressing forward with the calculation of peaking factors and ultimately PHDs was fairly simple. The peaking factor for ADD to MDD was calculated for each year (2012, 2013, and 2014) and then averaged across the three years to acquire the final peaking factor of 2.03. During the Steady-State Phase 1 of Water Modeling a diurnal demand pattern was not developed. Thus, a PHD could not be generated by which to calculate a MDD to PHD peaking factor; thus, a peaking factor of 2.00 was assumed based on industry norms. Using the ADD to MDD peaking factor of 2.03 for and the MDD and PHD peaking factor of 2.00 the following demands were calculated. Also, for the purpose of evaluating Water Age, an ADD to MinDD peaking factor of 0.44 was calculated. A summary of the calculations discussed within this section can be seen in **Table 3.4**.

Equation: $MDD = 2.03 \times ADD$

Equation: $PHD = 2.00 \times MDD$

Equation: $MinDD = 0.44 \times ADD$



TOWN OF ADDISON WATER MASTER PLAN

Table 3.4 – Existing ADD, MDD, Peaking Factor, and PHD Summary

Per Meter	2012			2013			2014			Averages		
	ADD	MDD	PHD	ADD	MDD	PHD	ADD	MDD	PHD	ADD (GPD)	MDD (GPD)	PHD (GPD)
COMLG	3,298	6,694	13,388	3,120	6,332	12,664	3,075	6,241	12,481	3,164	6,422	12,844
COMSM	661	1,342	2,683	620	1,258	2,516	609	1,236	2,472	630	1,278	2,557
H/M	13,165	26,720	53,441	14,178	28,776	57,552	14,015	28,445	56,890	13,786	27,980	55,961
INDLG	2,036	4,132	8,264	1,841	3,737	7,474	1,969	3,996	7,993	1,949	3,955	7,910
INDSM	395	802	1,603	438	889	1,777	309	627	1,254	381	772	1,545
IRRLG	4,876	9,896	19,793	4,344	8,817	17,634	3,173	6,439	12,878	4,131	8,384	16,768
IRRSM	2,026	4,113	8,226	1,687	3,425	6,849	1,442	2,927	5,854	1,719	3,488	6,976
MFLG	6,142	12,466	24,932	6,297	12,780	25,559	6,379	12,947	25,894	6,272	12,731	25,462
MFSM	2,357	4,785	9,569	2,012	4,083	8,167	1,676	3,402	6,803	2,015	4,090	8,180
SCH	5,706	11,580	23,161	4,185	8,493	16,986	4,119	8,360	16,720	4,670	9,478	18,956
SF	402	816	1,631	311	632	1,263	316	641	1,281	343	696	1,392
TOWN-WA	685	1,391	2,781	574	1,164	2,328	814	1,652	3,304	691	1,402	2,804
TOWN-IR	2,333	4,736	9,472	1,979	4,016	8,031	1,773	3,599	7,198	2,028	4,117	8,234

Town-Wide	2012			2013			2014		
	ADD	MDD	ADD to MDD Peaking Factor	ADD	MDD	ADD to MDD Peaking Factor	ADD	MDD	ADD to MDD Peaking Factor
TOTAL	5,160,314	9,649,000	1.870	4,735,816	11,091,000	2.342	4,409,955	8,278,000	1.877
Gal/Day	MinDD	ADD to MinDD Peaking Factor		MinDD	ADD to MinDD Peaking Factor		MinDD	ADD to MinDD Peaking Factor	
TOTAL	3,090,000	0.599		2,262,000	0.438		1,508,000	0.292	

Peaking Factors	
ADD to MDD Peaking Factor	2.03
MDD to PHD Peaking Factor	2.00
ADD to MinDD Peaking Factor	0.44



3.2.2 Allocation Process

As stated before, the allocation of demands was done per meter by user-type. A user-type map (**Figure 3.1**) was developed based upon a mixture of the zoning map, the user-type and address provided in the demand records, and information provided in the parcel Shapefile. The main purpose of developing this map was to help expedite the process of allocating the correct (based on user-type) demands to the appropriate junction/node in the water model. A combination of Thiessen Polygons (from WaterGEMS) and GIS manipulation (spatial join) was used to develop a Shapefile in GIS containing the Water Model junctions/nodes to which the corresponding demands were allocated. The allocated demands were then re-imported into WaterGEMS using the LoadBuilder tool and assigned to the corresponding junction in the Water Model, and an ADD-Existing Demand alternative was created.




Figure 3.1

**Town of Addison
User-Type Map**






3.2.3 Diurnal Demand Pattern

The basis for the development of the diurnal demand pattern was 72 hours of recorded SCADA data acquired from the Town of Addison. The SCADA data included recorded readings every half-hour of which pumps were on/off, pump flow, pump Total Dynamic Head, and Ground Storage Tank levels for each pump station (Celestial and Surveyor), as well as, Elevated Storage Tank levels for each EST (Addison Circle and Surveyor). From this data, calculations were performed to determine net system-wide demands for every half-hour. Demands were calculated by first calculating an approximate elevated storage tank flow rate based on the change in tank elevation over each 30 minute period and then adding or subtracting it from the pump flow rate readings. Demands were calculated for every half-hour over the course of 3 days for each time interval (12:00 am, 12:30 am, 1:00 am, 1:30 am, etc.). Next, the average of all of the demands over the course of the 3 days was evaluated to determine an ADD which was then used to calculate a diurnal demand factor by dividing the demand for each 30 minute interval by the ADD. Finally, once this was accomplished a Diurnal Demand Factor Curve was generated as can be seen in **Figure 3.2 – Diurnal Demand Pattern**. The Diurnal Demand Pattern was then inputted into the Water Model and applied to the various demand alternatives as the basis for the Extended Period Simulation (EPS). A brief understanding of the Diurnal Demand Pattern is as follows: the peak hour is 3:30 am and this is understood to be the timeframe in which the Town irrigates, and the second peak hour is around 10:00 – 11:00 pm which corresponds with the times in which the many restaurants and bars within Addison would be closing down and cleaning up with many toilets being flushed and dishes being cleaned.



TOWN OF ADDISON WATER MASTER PLAN

Figure 3.2 – Diurnal Demand Pattern





3.2.4 Population & Land Use

Taking a brief side-tangent, a discussion on population and land use as it relates to demand and the number of connections within the Town is beneficial for getting an idea of the unique nature of Addison's population, diurnal demand curve, and demands in general. Addison is a unique town in that residential zoning by land area accounts for only about 19% of the Town's total land area, while at the same time the commercial zoning by land area accounts for 45% of the total land area. This land user-type distribution results in a smaller residential population, but a much higher day time and evening population because of the many restaurants, stores, and offices within the Town. From this, it can be better understood why the normal diurnal curve peak times do not occur in Addison. Therefore, a normal demand per capita ratio is not an effective means of determining or projecting future demands within the Town because it does not account for the day time population boom or for the large commercial land area which results in relatively higher than normal irrigation demands. Population growth is limited, as well, because the Town is nearly 95% built-out already. At this point, population estimates vary because the last census conducted was in 2010; however thanks to the North Central Texas Council of Governments (NCTCOG) population estimates help to paint a picture of Addison. See **Table 3.5** below for a breakdown of the population estimates and future population projections for Addison. Future population projections were calculated using an estimated population per connection ratio for each population estimate method.



Table 3.5 – Existing ADD, MDD, Peaking Factor, and PHD Summary

Population Projections Based on 2010 Census				
<i>Year</i>	<i>Timeframe</i>	<i>Number of Connections</i>	<i>Approximate Population</i>	<i>Population/Connection</i>
2015 (2010)	Existing	3,677	13,056	3.55
2020	5-yr	3,731	13,248	3.55
Buildout		3,796	13,479	3.55

Population Projections Based on 2013 NCTCOG Pop. Estimates				
<i>Year</i>	<i>Timeframe</i>	<i>Number of Connections</i>	<i>Approximate Population</i>	<i>Population/Connection</i>
2015 (2013)	Existing	3,677	14,114	3.84
2020	5-yr	3,731	14,321	3.84
Buildout		3,796	14,571	3.84

Population Projections Based on 2014 NCTCOG Pop. Estimates				
<i>Year</i>	<i>Timeframe</i>	<i>Number of Connections</i>	<i>Approximate Population</i>	<i>Population/Connection</i>
2015 (2014)	Existing	3,677	15,180	4.13
2020	5-yr	3,731	15,403	4.13
Buildout		3,796	15,671	4.13

Population Projections Based on 2015 NCTCOG Pop. Estimates				
<i>Year</i>	<i>Timeframe</i>	<i>Number of Connections</i>	<i>Approximate Population</i>	<i>Population/Connection</i>
2015 (2015 Projection)	Existing	3,677	15,530	4.22
2020	5-yr	3,731	15,758	4.22
Buildout		3,796	16,033	4.22



3.2.5 Future Water Demand Development

Using the 5-yr Period and Buildout Future Land Use plans provided by Addison, areas of planned development or redevelopment were determined. Once the areas of planned development were determined, the appropriate user-type demands were selected that matched the proposed development type. Then, review of the existing infrastructure near the proposed development was conducted, and assumptions were made regarding the infrastructure improvements needed and demands were appropriately allocated per meter based on user-type. An assumption was made that the existing ADD per user-type by meter will stay essentially the same regardless of future development. A comparison of the town-wide demands can be seen below in **Table 3.6**. A visual map depicting the future land development can be seen in **Figure 3.3**.

Table 3.6 – Existing ADD, MDD, Peaking Factor, and PHD Summary

Year	ADD (MGD)	MDD (MGD)	PHD (MGD)
Existing (2015)	4.83	9.81	19.61
5-yr Period (2020)	5.16	10.47	20.95
Buildout	5.29	10.74	21.49




Figure 3.3

**Town of Addison
Future Development Map**





3.3 Water Age Information

The purpose of the development of the water age portion of the Water Model is to enhance the hydraulic model so that water age analyses can provide a simple, nonspecific measure of overall water quality, evaluating storage tank turnover impacts on the distribution system's water quality, and providing evaluation of the current flushing program. Unfortunately because of the lack of data, the initial water age being supplied by DWU to Addison is unknown. Thus, for the purposes of modeling, the initial water age was set to a baseline of zero from which relative water age was determined. This establishment of a baseline age of zero makes it easier to evaluate the addition of the DWU water age in the future. Also, in order to effectively evaluate a correlation between water age and chlorine residual, record chlorine residual data was obtained for the timeframe: January 2015 to September 2015. This data served as the basis for developing the water age breakpoint (i.e. the time at which the water age results in less than desirable water quality). Further discussion regarding the Water Age Analysis can be found in **Section 5.4**.

4.0 WATER MODEL CALIBRATION AND VALIDATION

A water model is only as good as its ability to, as closely as possible, accurately mimic the real-world conditions. Once the model was built, components were added, and inputs were added, a big step in preparing the water model to accurately predict real-world conditions was the process of calibration and validation. In this section a summary of the calibration steps used to finalize development of the model will be provided and outlined. Location of the fire hydrants in the field used for the flow tests, the test results, the iterative model improvement process, and the final results, variances, and accuracies will be discussed within this section.

4.1 Fire Flow Tests

The first step in the calibration process was collection of Fire Flow Test data from the field. The Fire Flow Test results stand as the basis from which the Water Model was calibrated against real-



world conditions. Thus, it was important to collect data that represented the system as accurately and broadly as possible. This first step was selecting proper locations for performing the fire flow test locations and selecting which fire hydrants would act as the residual hydrants and which one would be the flow hydrant. The second step was the analysis of the initial results. Discussed in this section will be the locations of the Fire Flow Test requests and the type of data collected.

4.1.1 Locations & Maps

It was important to collect data that accurately represented the water system, and thus, eleven (11) fire flow test locations were diligently selected within the system. The locations were distributed fairly evenly throughout the system in order to capture a representative view of the hydraulic conditions of the water system. Please see a locator map of the test locations in **Figure 4.1**. At each location one (1) flow hydrant and two (2) residual hydrants were selected to be measured. For the sake of accuracy, the two (2) residual hydrants at each test location were located on separate water mains for the purposes of capturing the true picture of the effects of operating the flow hydrant. Results from the fire flow tests can be found in the fire flow test request maps package in **Appendix D** for each specific location.




Figure 4.1

**Town of Addison
Fire Flow Test Locations**





4.1.2 Data Collected

At each test location, the following data was collected.

Table 4.1 – Fire Flow Test Data

Fire Flow Test Data		Date: _____	Time: _____
Boundary Conditions at Time of Test			
Surveyor GST Elevation (ft) _____	Surveyor EST Elevation (ft) _____		
Celestial GST Elevation (ft) _____	Addison Circle EST Elevation (ft) _____		
Surveyor Pump Station Conditions		Celestial Pump Station Conditions	
Pump 1: On or Off ; If On, Flow = _____ gpm	Pump 1: On or Off ; If On, Flow = _____ gpm		
Pump 2: On or Off ; If On, Flow = _____ gpm	Pump 2: On or Off ; If On, Flow = _____ gpm		
Pump 3: On or Off ; If On, Flow = _____ gpm	Pump 3: On or Off ; If On, Flow = _____ gpm		
	Pump 4: On or Off ; If On, Flow = _____ gpm		
	Pump 5: On or Off ; If On, Flow = _____ gpm		
Fire Flow Test Results			
RESIDUAL Fire Hydrant No. 1	RESIDUAL Fire Hydrant No. 2	FLOW Fire Hydrant	
Static Pressure = _____ psi	Static Pressure = _____ psi	Gauge Distance From	
Gauge Distance From	Gauge Distance From	Hydrant Top Nut = _____ ft	
Hydrant Top Nut = _____ ft	Hydrant Top Nut = _____ ft	Pitot Pressure = _____ psi	
Residual Pressure = _____ psi	Residual Pressure = _____ psi	Flow = _____ gpm	

From this data, scenarios were set up in the Water Model to mimic/match the boundary conditions in the field and specific demand alternatives were created to match the water demands being seen in the field at the time of the fire flow tests. The model was then run and the model results were compared against the field results.

4.1.3 Results

For the fire flow test scenarios, the recorded field fire flow (in gpm) was applied to the appropriate hydrant in the Water Model. The hydraulic criteria that functioned as the basis of comparison were the hydraulic gradelines at each hydrant. The hydraulic gradeline for the test hydrants was determined by converting the field measured pressure (in psi) to a pressure head (in feet) and adding it to the elevation of the pressure gauge to acquire the hydraulic grade (in feet). The results of the model runs were then analyzed against the results of the field tests, and minor adjustments such as changing Hazen-Williams C-values, pipe materials, and revising pipe connectivity were made until the model results were within a tolerable variance from the field



test results. A spreadsheet was developed for the purpose of comparing the field test results against the water model scenario run results for each hydrant. Acceptable hydraulic gradeline variances were as determined by the AWWA M32 – Computer Modeling of Water Distribution Systems manual. The hydraulic gradeline variance recommended by the manual is $\pm 5 - 10$ feet (2.2 – 4.3 psi).

4.2 Pump Curve Evaluations

Also, during the model calibration process because of some discrepancies between the recorded SCADA data and provided pump curves, a number of iterations were required to obtain accurate pump curves that represented the real-world functioning of the pumps. Multiple GST draw-down (drain-down) tests were conducted at each pump station to acquire real-world pump flow data with which to compare against the pump curves that had been provided. During these tests, most of the pump curves were verified to be correct, but it was determined that the SCADA readings at Celestial Pump Station for lower flows (only Pump #4) were roughly 800 gpm higher than what was actually being pumped through the pumps (as shown by the pump curves). Also, at Surveyor pump station it was verified, when compared against the results of the draw-down test, that the SCADA readings in the field were slightly inaccurate. It was, also, discovered that the pump curves (all three (3) pumps) provided for Surveyor Pump Station were slightly incorrect, and adjustments were made to the pump curve definitions in the Water Model to correct the discrepancy. **Appendix C** contains copies of the pump curves for reference.

4.3 Iterative Calibration Process

The process used to calibrate the Water Model was an iterative one in which fire flow tests were conducted in the field and mimicked in runs in the water model by setting boundary conditions to match those present during the field fire flow tests. During this iterative process, a number of discrepancies were discovered in the field data that had been collected, and multiple iterations of fire flow tests had to be conducted at the locations in which discrepancies were found. Field



test locations #2 & # 8 required one round of re-testing and #4 & #6 required two rounds of re-testing to finally acquire hydraulically accurate data. Iterative adjustments were then made to physical components of the Water Model until results of the model runs when compared against the field test results were within the acceptable variance range for all eleven (11) test locations.

5.0 HYDRAULIC ANALYSIS

Hydraulic analysis of the water distribution system was broken into two (2) phases: 1.) Steady-State Analysis and 2.) Extended Period Simulations & Water Age Analysis. From here on out the Steady-State Analysis will be referred to as Phase 1 of the water modeling and the EPS & WAA will be referred to as Phase 2.

Initially, in Phase 1 of the water modeling, hydraulic deficiencies within the Town of Addison's water distribution system were evaluated using steady-state hydraulic analyses. This section discusses the steady-state hydraulic analyses design criteria used to evaluate the four (4) demand alternatives (ADD, MDD, PHD, and MDD + Fire Flow) for the existing, 5-yr period (2020), and Build-Out Conditions. Also discussed in this section is the process of setting up run alternatives and scenarios in WaterGEMS to perform the aforementioned analyses. Finally, the results of the hydraulic analyses led to the ultimate purpose of the water modeling: the identification of system infrastructure improvements needed to bolster the hydraulic functioning of the water distribution system to meet hydraulic design criteria.

Next, in Phase 2 of the water modeling, the system infrastructure improvements identified to meet hydraulic design criteria were further evaluated using a diurnal demand pattern based model using extended period simulations. Existing system operational controls/settings, storage and pumping capabilities, and emergency management scenarios were, also, evaluated using the



EPS model runs. Finally, the water age analysis was used to develop a general picture of the system’s water quality, evaluate the flushing program, and evaluate tank turnover.

Further evaluation and summary of the identified system infrastructure improvements or Capital Improvement Projects (CIP) is discussed in **Section 6.0 Capital Improvement Projects (CIP) Plan**.

5.1 Design Criteria

As the base for evaluating the hydraulic conditions of the water distribution system, design criteria for minimum & maximum allowable velocities, head-losses, pressures, and minimum fire flow rates were specified for normal steady-state (static) and fire flow demand scenarios. Under normal steady-state demand scenarios (i.e. without fire-flows), maximum velocities, maximum head losses, minimum pressures, and maximum pressures were used to evaluate the hydraulics of the water model. Under fire flow demand scenarios, minimum fire flow rates specified, maximum velocities, and minimum residual pressures were used to evaluate the water model hydraulics. A summary of the hydraulic design criteria can be seen below.

Table 5.1 – Hydraulic Design Criteria

Hydraulic Criteria	Demand Condition	
	ADD, MDD, PHD	MDD + FF
Max Velocity (fps)	7	7
Max Head Loss (ft/ft)	4/1000 (or 0.004)	N/A
Min Pressure (psi)	40	25
Max Pressure (psi)	100	100
Min Specified Fire Flow (gpm)	N/A	1000

The aforementioned design criteria were used to evaluate all pipes and junctions within the water model – water distribution system.



5.2 Phase 1: Steady-State Hydraulics

The Steady-State Hydraulic Analysis represents a snapshot in time of the water distribution system in which the established initial conditions of the water model greatly influence the results of a model run. One benefit of Steady-State hydraulics is that the model run is fairly simple and hydraulic deficiencies can be more easily identified and infrastructure improvements added to remedy said deficiencies. However, the nature of running the model as a snapshot in time places more limitations on the model's ability to mimic real-world conditions and places more importance on the initial conditions which effectively control the response of the model. Thus, in evaluating steady-state hydraulics it was critical to establish initial conditions representing the potentially worst-case hydraulic scenarios within the system. Steady-state model runs were conducted for twelve (12) demand alternatives by which the hydraulic design criteria were evaluated; the twelve (12) demand alternatives are a function/multiplication of the three (3) timeframes and the four (4) demand conditions. Using the capabilities of WaterGEMS, demand scenarios were created for each demand alternative and these scenarios and the results of the model runs are discussed below. Within WaterGEMS, scenarios were created to mimic real-world conditions using varied active topologies, physical, demand, initial settings, operational, and fire flow alternatives created within the Water Model. The appropriate alternatives were selected for the twelve (12) steady-hydraulic scenarios. See a list of the scenarios below in order of increasing stress applied on the system.

1. ADD – Existing
2. MDD – Existing
3. PHD – Existing
4. MDD + FF – Existing – Fire Flow Analysis
5. ADD – 5-yr
6. MDD – 5-yr
7. PHD – 5-yr



- 8. MDD + FF – 5-yr – Fire Flow Analysis
- 9. ADD – Buildout
- 10. MDD – Buildout
- 11. PHD – Buildout
- 12. MDD + FF – Buildout – Fire Flow Analysis

As previously mentioned, in order to conservatively evaluate the hydraulics of the system, a potentially (within reason) worst-case initial settings alternative was created for each demand condition (ADD Operational Settings, MDD Operational Settings, and PHD Operational Settings) because the steady-state model provides only a snapshot in time and thus the initial settings have great influence on the hydraulics of the system. Once the scenarios were properly setup, the model was run for each in order of increasing stress on the system (see the list above). The results were compared against the design criteria, and areas of hydraulic failure were determined and visually depicted using color-coding capabilities within WaterGEMS. Then, potential improvements were identified and added to the water model as active topology and physical alternatives, the scenarios were updated, and the model was re-run with the proposed improvements to verify if the identified improvements aided the distribution system in meeting hydraulic design criteria. This iterative process was performed until a list of improvements had been identified. Below is a summary and brief statistical analysis of the results of the steady-state hydraulics analyses. The following demand scenarios resulted in hydraulic failure and required the number of improvement projects to meet the design criteria.

Table 5.2 – Statistical Summary of Steady-State – CIP Identified

Demand Scenario	No. of Improvements
PHD – Existing	3
MDD + FF – Existing – Fire Flow Analysis	14
PHD – 5-yr	2
City Requested*	3
Total No. of Identified Improvements	22

*Based upon city maintenance records and recommendations; these improvement projects were not needed to meet hydraulic design criteria.



It should be noted that any capital improvement projects needed to handle hydraulic failure were incorporated in order of increasing stress on the system. This is the reason that less improvements were identified for some of the higher hydraulic stress scenarios because the hydraulic needs of the system had already been improved during the earlier stages of the modeling process. Further discussion, details/descriptions, analysis, and prioritization of the capital improvement projects can be found in **Section 6.0 – Capital Improvement Projects (CIP) Plan**.

5.3 Phase 2: Extended Period Simulations

Among other things, the extended period simulations were used in Phase 2 of the water modeling to re-evaluate and refine the CIP plan. Through the process of re-evaluating and refining the CIP plan it was determined that the proposed CIP improvements identified as part of the Phase 1: Steady-State Hydraulics all still applied. Seven (7) demand alternatives were evaluated using the EPS model and they are listed below.

1. ADD – Existing
2. MDD – Existing
3. ADD – 5-yr
4. MDD – 5-yr
5. ADD – Buildout
6. MDD – Buildout
7. MinDD [Minimum Demand Condition used to Evaluate Water Age]

The reason that the PHD is not listed here is because the running of an extended period simulation establishes the peak hourly demand based upon the time along the diurnal pattern. Fire flow analyses for the EPS was, also, not evaluated because the diurnal pattern applied for maximum daily demands results in demands as mentioned before that reach the peak hourly demands and thus result in higher demands than a fire flow scenario.



5.3.1 Calibration & Validation

In addition to the steady-state fire-flow tests model calibration process which was used to calibrate the hydraulic conditions of the model to mimic real-world conditions, an extended period simulation calibration process needed to be accomplished to ensure the water model’s operational criteria, pumps, tanks, and demands functioned properly over time. The calibration and validation of these items was done by comparing the demand, pump, and EST flow rates in the model against the real world data which was the same data acquired by the SCADA system used to build the diurnal demand pattern. In the water model, the initial boundary conditions (tank elevations, etc.) and pump operational criteria were set to match the real-world boundary conditions as recorded via SCADA. From this a water model scenario was setup; the model was run; and the results compared against real-world conditions. The model operational criteria and components were then iteratively adjusted until the water model results more accurately reflected real-world data. After a few minor adjustments, a calibrated model was acquired. Validation of this model ensued

5.3.2 Steady-State CIP Plan Evaluation

Two (2) new CIP options were identified to ensure the system does not exceed the maximum head loss as defined in **Table 5.1** in the **Design Criteria Section**. Below is a statistical summary of the Extended Period Simulations (EPS) demand scenarios that contributed to the identified improvement projects needed.

Table 5.3 – Statistical Summary of Extended Period Simulation – CIP Identified

Demand Scenario	No. of Improvements
MDD – Existing – EPS Peak Hour (~4 am)	2
Total No. of Identified Improvements	2

Also, the EPS model was used to evaluate the functional operational controls currently in use within the Town, analyze in greater depth the existing storage and pumping capabilities, and



establish recommendations for emergency management by performing model runs for potential emergency scenarios. All of these topics will be discussed within this section.

5.3.3 Operational Controls Evaluation

Capabilities of the water model provided a means by which to evaluate operational controls by which Addison can operate its pump stations. Per discussion with Addison it was determined that due to the complexity of having two (2) elevated storage tanks to manage, the operational control criteria are manually modified fairly often in order to ensure proper hydraulics and water quality (as will be discussed in Section 5.4). Operations are, also, modified based on the time of the year to accommodate higher or lower demands. This being said, it was hard to pinpoint a base set of consistently used operational criteria of which to evaluate; however, a rough imitation of the current (as of the date of this report) operational controls was built into the model to serve as the basis by which to begin evaluating the controls. The current operational controls were evaluated against the seven (7) demand alternatives (listed previously). While performing the evaluations, the ground and elevated storage tank low-level and high-level water alarm, as well as, proper pump functioning were the model criteria used to determine if the operational controls would work. From this evaluation, it was determined that the current operations suffice for the ADD – Existing (EPS) and the MinDD (WAA) demand alternatives; however, as suspected, the current operational controls are not sufficient to meet the needs of the remaining demand alternatives. Thus, alternative operational controls were developed to meet the needs & optimize the functioning of the system for each demand alternative scenario. Five (5) distinct operational control setting alternatives were developed. The developed operational control setting parameters are set relative to the Addison Circle EST levels and are applicable when both elevated storage tanks are online. A summary of the control alternatives and the timeframe in which they should be implemented can be seen below.



Table 5.4 – Operational Control Settings Summary

Operational Controls		Demand Scenario	Normal Applicable Timeframe
Setting A	Average Demand	ADD (Existing), ADD (5-yr), & ADD (Buildout)	Fall & Spring Months - Normally October thru November & April thru May
Setting B.1	High Demand (Existing)	MDD (Existing)	Summer Months - Normally June thru September (for Existing)
Setting B.2	High Demand (5-yr)	MDD (5-yr)	Summer Months - Normally June thru September (for 5-yr Period)
Setting B.3	High Demand (Buildout)	MDD (Buildout)	Summer Months - Normally June thru September (for Buildout)
Setting C	Low Demand	MinDD	Winter Months - Only the Lowest Demand Periods - Normally December thru March

Detailed parameters of each of the aforementioned operational control settings can be seen in **Appendix E**.

5.3.4 Storage and Pumping Evaluation

As a part of the scope of Phase 1 of the Water Modeling, preliminary storage and pumping capabilities were analyzed against the baseline minimum requirements of TCEQ. According to the TCEQ minimum storage capacity (gallons per connection) and pumping minimum capacities (gpm), Addison’s storage and pumping capabilities are more than sufficient. The following tables show the TCEQ requirements and subsequent Addison capabilities for both storage and pumping.

Table 5.5 – TCEQ Storage Tank Capacity Requirements

TCEQ Requirements*	
TCEQ Total Storage Requirements (gallons per connection)	200
TCEQ Elevated Storage Requirements (gallons per connection)	100

*According to 30 TAC Part 1 §290.45(b)(2)(F)&(G)



Table 5.6 – Existing Storage Tank Analysis

Existing Storage Analysis		
Type	Facility	Volume (MG)
Elevated	Addison Circle EST	1.0
Elevated	Surveyor EST	1.5
Ground	Surveyor GST	2.0
Ground	Celestial GST	6.0
Total		10.5
<i>Estimated Number of Existing Connections*</i>		3677
<i>Estimated Number of 5-yr Period Connections**</i>		3731
<i>Estimated Number of Buildout Connection**</i>		3796
Existing Total Storage Capacity (gallons per connection)		2856
Existing Elevated Storage Capacity (gallons per connection)		680
5-yr Period Total Storage Capacity (gallons per connection)		2814
5-yr Period Elevated Storage Capacity (gallons per connection)		670
Buildout Total Storage Capacity (gallons per connection)		2766
Buildout Elevated Storage Capacity (gallons per connection)		659

*Approximated from coordination with Phil Kagarice and Addison Billings Dept.

**Determined by adding the projected number of connections (meters) that will be added for the future development.

Table 5.7 – TCEQ Pumping Capacity Requirements

TCEQ Requirements*	
Elevated Storage Capacity	Service Pumping Capacity Requirement
> 200 gallons per connection	Two service pumps with a minimum combined capacity of 0.6 gpm per connection at each pressure plane
< 200 gallons per connection	The lesser of (a) or (b):
	(a) Total pumping capacity of 2.0 gpm per connection
	(b) Total pumping capacity of at least 1,000 gpm and the ability to meet peak hourly demands with the largest pump out of service

*According to 30 TAC Part 1 §290.45(b)(2)(F)&(G)



Table 5.8 – Existing Pumping Capacity Analysis

Existing Service Pumping Capacity		
Pump		Capacity (gpm)
Celestial Pump 1		7,000
Celestial Pump 2		3,200
Celestial Pump 3		7,000
Celestial Pump 4		2,000
Celestial Pump 5		7,000
Surveyor Pump 1		3,850
Surveyor Pump 2		3,000
Surveyor Pump 3		3,000
Total Current Capacity		36,050⁽³⁾
Worst Case Scenario Pump Capacity (Celestial PS - Pump #2 & Pump #4)⁽¹⁾		5,200 ⁽³⁾
Worst Case Scenario Pump Capacity (Surveyor PS - Pump #2 & Pump #3)⁽¹⁾		6,000 ⁽³⁾
Estimated Number of Existing Connections⁽²⁾		3,677
Estimated Number of 5-yr Period Connections⁽²⁾		3,731
Estimated Number of Buildout Connections⁽²⁾		3,796
Celestial Pump Station	Worst Case Scenario Pump Capacity [gpm/connection] - Existing	1.41
	Worst Case Scenario Pump Capacity [gpm/connection] - 5-yr	1.39
	Worst Case Scenario Pump Capacity [gpm/connection] - Buildout	1.37
Surveyor Pump Station	Worst Case Scenario Pump Capacity [gpm/connection] - Existing	1.63
	Worst Case Scenario Pump Capacity [gpm/connection] - 5-yr	1.61
	Worst Case Scenario Pump Capacity [gpm/connection] - Buildout	1.58

(1) The Worst-Case/Minimum Scenario is as determined by the TCEQ Requirements.

(2) The estimated number of connections (meters) is the same as depicted in **Table 5.6**.

(3) Total Capacity = Summation of the pumps operating point capacities.

Using the capabilities of a time based – EPS model – further analysis of the storage tank capacities was accomplished by running model scenarios in which operational and initial worst-case situations were evaluated to see how the water system storage tank, particularly elevated



storage tank, elevations and volumes fluctuate over time. The water model reveals that Addison's storage capabilities are more than sufficient to meet the hydraulic and water quality needs of the Town. Along these same lines, the pumping capabilities when modeled are more than sufficient to meet the hydraulic and water quality needs of Addison. Potential scenarios such as tanks being offline and pumps being out of service represent points in time that emergency management must be implemented and of which is discussed in the next section.

5.3.5 Emergency Management Evaluation

A multitude of potential emergencies exist: periods of extended drought; extreme fire events; natural disasters including tornados, lightning strikes, ice storms, etc.; civil unrest/terrorist attacks; airplane crashes; hazardous material spills; extended power outages; and major maintenance outages are just a few of the many. Many of these emergencies have the potentiality of directly affecting the stable functioning of the assets and facilities present with Addison's water distribution system. Pumps, tanks, waterlines, valves, hydrants, etc. are all assets that to varying levels of degree that when damaged can negatively affect the system in its ability to meet the hydraulic needs of the Town. Adverse effects to the proper functioning of Addison's elevated storage tanks and pump stations will result in the most easily recognizable and negative impacts to the hydraulic and water quality needs of the system. Thus, potential emergency scenarios were evaluated in the water model for hindrance to proper functioning of the two (2) ESTs and the two (2) pump stations. A breakdown of the emergency management scenarios evaluated and the appropriate responses to remedy or at the very least manage the emergencies can be seen in the table below. It should be noted that the emergency scenarios discussed and evaluated herein are not comprehensive of all the potentialities. Thus, the Dallas County Hazard Mitigation Action Plan and the Drought Contingency Plan should serve as the basis for more dramatic emergencies not able to be managed by modifying operations of the system. Also, due to the higher pressure plane on which Addison is operating, the emergency connections with DWU will require pumps to deliver flow from DWU to Addison. Please see Figure 2.1 for a map showing the location



of the aforementioned emergency connections. Scenarios requiring operation of these emergency connections were evaluated in the water model, and it was determined that by adding emergency (temporary-use) pumps the hydraulic needs of Addison can be met. All emergency management scenarios were evaluated using the Maximum Daily Demands at Buildout which represent the worst-case demand conditions. Water quality concerns were not considered during these emergency management scenarios. However, during emergency management a general evaluation is that the water quality will not vary dramatically from normal operations if the recommended strategies are adhered to because the same tank boundary conditions and hydraulic needs are being met in both.

Table 5.9 – Emergency Management Scenarios

Scenario ⁽¹⁾	Remedy/Management Strategy
Surveyor PS Down	Modify the Operational Control Settings at Celestial PS to Operate without Surveyor
Celestial PS Down ⁽²⁾	Open up one of the DWU Emergency Connections and Supply Water using an Emergency Pump ⁽³⁾
Addison Circle EST Down	Modify the Operational Control Settings at Celestial PS to Operate off of the Surveyor EST Levels
Surveyor EST Down	Modify the Operational Control Settings at Celestial PS to Operate with Slightly Higher Addison Circle EST Levels
If a more dramatic emergency occurs (such as loss of both Pump Stations and both Elevated Storage Tanks, etc.) than please follow the guidelines spelled out in the Dallas County Hazard Mitigation Action Plan.	
If the emergency is drought related than follow the strategy guidelines specified in the drought contingency plan.	

Notes:

(1) If the emergency situation involves the loss of a single PS and a single EST than combine the strategies.

(2) This applies when none of the big Celestial Pumps (1, 3, & 5) are in operation. If any of the big Celestial Pumps are in service than operations can continue as normal.

(3) Emergency Pump will have to be properly selected at the time of the need based on the Hydraulic conditions of the system (i.e. demands and time of year).



5.4 Phase 2: Water Age & Quality Analysis

The diurnal pattern used to develop the extended period simulation model served as the basis by which the water age (over time) is analyzed. From these analyses, a general picture of the water quality within the Town of Addison was surmised based on the water age. In junction with the water age analysis, a chlorine residual (water quality) data evaluation was performed on the chlorine residual data acquired for January 2015 to September 2015. Water age analyses provided were used to provide flushing program recommendations and evaluate operations for improving tank turnover processes. These items will be discussed within this section.

5.4.1 General System Water Quality

A general picture of the water quality of the distribution system has been evaluated using a combination of water age results from the model and chlorine residual data. Minimum day demands (MinDD) result in the highest water age. See **Figure 5.1** for a map depicting the water ages throughout the system for the MinDD worst-case scenario prior to system buildout and **Figure 5.2** for after the proposed CIP improvements have been constructed. In junction with a water age analysis, a chlorine residual data evaluation was conducted for residuals acquired from January 2015 to September 2015. **Figures 5.1 & 5.2**, also, depict the location of the sampling locations. **Appendix F** contains a tabular summary of the residual data and graphical depictions of the acquired data. As seen on the map when minimum day demands are simulated the water age ranges from 0 to 6+ which is deemed to be too high based upon the results of the chlorine residual evaluation. Analysis and evaluation of the water age in the model and the chlorine residual data leads to a number of conclusions:

1. Water quality in the northern, southwestern (Vitruvian area), and southern (Inwood and DNT area) portions of Addison is lower than ideal.
2. Low chlorine residuals at the Surveyor EST seem to correlate with lower chlorine residuals throughout the system (see the graphs in **Appendix F**).



3. Chlorine residual and water ages at the pump stations do not appear to be the main contributors to the water quality issues; whereas, the water age and quality within the elevated storage tanks seem to greatly effect water quality.
4. A closer look at the water age results in the model reveal that many of the high water age problems (and thus low water quality) occur at dead-end mains and/or un-looped mains.

5.4.2 Water Quality Improvement Recommendations

A list of recommendations to improve water quality within the Town of Addison is as seen below:

1. Implement the two (2) capital improvement projects determined via the water age analysis; description and evaluation of each option can be seen in **Section 6.0**.
2. Setting aside annual operations and maintenance budget for looping of dead-end lines.
3. Operational control Setting C (see **Appendix E**) should be implemented during periods of low water demands (i.e. winter months) to allow greater tank turnover.
4. Install a chlorine booster station at Surveyor Elevated Storage Tank to decrease water age and boost chlorine residual.
5. Combine increased flushing operations during periods of low demand with deep cycling of the elevated storage tanks.




Figure 5.1

**Town of Addison
Minimum Day Demand (MinDD)
Water Age Map Before CIP**






Figure 5.2

**Town of Addison
Minimum Day Demand (MinDD)
Water Age Map After CIP**





6.0 CAPITAL IMPROVEMENT PROJECTS (CIP) PLAN

From the hydraulic analyses, a water infrastructure capital improvement project (CIP) plan was developed to ensure hydraulic design criteria within the system are met so Addison can continue to deliver great water distribution services. A timeframe breakdown of the CIP plan is as follows: existing improvements, 5-yr (2020) improvements, and Build-Out improvements. As discussed previously, these three (3) timeframes were analyzed for ADD, MDD, PHD, and MDD + FF independently using scenarios in the water model, and areas/components that failed to meet design criteria were improved by a combination of line upsizing, replacing aging infrastructure, and new infrastructure (additional looping).

After a number of model-run iterations, a list of identified capital improvement projects was compiled (**Table 6.1**), with the projects being in no particular order. Then, the process of evaluating each CIP option was begun by generating opinions of probable construction cost for each project, performing risk-based analyses on each project, and preparing a summary table (project plan priority matrix) that was populated with information describing each CIP option. See **Appendix G** for the project plan priority matrix. For visual purposes, a map (**Figure 6.1**) was generated to show the geographic location of the identified improvements. It should be noted that only a general location of the improvements was identified; precise alignments and specific locations of the capital improvement projects will have to be included as part of the infrastructure design plans. As aforementioned, combined with the improvements needed to meet hydraulic design criteria, three (3) projects (Nos. 1, 18, & 19) are the result of maintenance records and were added to the list at the recommendation of Addison.



Table 6.1 – Identified Capital Improvement Projects (CIP)

Option No.	Length (~ LF)	Option Description (including location)
1	3300	City Recommended: New 12-in PVC Water Main Loop (Apt. Complex in NW Corner of Town)
2	8	Upsize Short Connection from 6-in to 8-in (North of Beltline on Quorum)
3	101	Upsize 8-in DI to 10-in PVC Water Main Near 36-in to 8-in Connection (SE Corner of Village on the Parkway)
4	23	Upsize 12-in PVC to 16-in DI Water Main Connection Between 36-in & 12-in Main (South of Beltline on Quorum)
5	210	Upsize 6-in PVC to 8-in PVC Water Line for Lateral (Off of Claire Chennault Street)
6	1271	Upsizing 6-in CI to 8-in PVC Water Main (Lake Forest Drive)
7	1829	Upsize 6-in PVC to 8-in PVC Water Main (Shadwood Apartments - Sydney Dr & Marsh Ln)
8	947	New 6-in PVC Water Main Loop (Talisker Apartments - off of Vitruvian Pkwy)
9	48	Upsize 6-in Unk to 8-in PVC Water Main (Glenn Curtiss Dr & Addison Rd)
10	1388	Upsize 6-in Unk to 8-in PVC Water Main (Apartment Complex at NE Intersection of Addison Rd & Westgrove Dr)
11	168	Upsize 8-in PVC to 12-in PVC Water Main (Excel Telecommunications Service Center to Addison Rd)
12	813	New 10-in PVC Water Main Loop (One Hanover Park Offices to Excel Pkwy along DNT)
13	30	Upsize 6-in Unk to 8-in PVC Water Main (Quorum Office Building #2)
14	144	Upsize 8-in PVC to 10-in PVC Water Main (Quorum Office Building #2)
15	73	Upsize 8-in PVC to 10-in PVC Water Main (Lateral off of Quorum Dr)
16	4254	Upsize 8-in CI to 10-in PVC Water Main (Running N to S from Beltline Rd to George H.W. Bush Elementary)
17	1617	Replace 8-in CI with 8-in PVC Water Main (Intersection of Beltway Dr & Beltline Rd - Beltway Office Park)
18	583	City Recommended: Replace 8-in DI with 8-in PVC Water Main (Prestonwood Place Shopping Ctr near Intersection of Beltline Rd & Montfort Dr)
19	1499	City Recommended: Replace 8-in CI with 8-in PVC Water Main (Greenhaven Village Shopping Ctr at Intersection of Marsh Ln & Spring Valley Rd)
20	35	Upsize 8-in Unk to 10-in PVC Water Main (The Madison - 15851 Dallas North Parkway)
21	28	Upsize 8-in PVC to 12-in PVC Water Main (The Wellington Square - Southern Edge of Addison)
22	20	Upsize 8-in PVC to 12-in PVC Water Main (Millenium Phase I - NW Intersection of Arapaho & DNT)
23	1144	Upsizing 16-in RCCP to 24-in RCCP (in Belt Line Rd between Addison Rd and Quorum Dr)*
24	116	Upsizing 16-in DI to 24-in RCCP (Intesection of Belt Line Rd and Quorum Dr)*
25	149	New 8-in PVC Water Main Loop (Excel Telecommunications Service Center to Addison Rd)**
26	93	New 8-in PVC Water Main Loop (FedEx Store - 4901 Airport Pkwy)**

* Extended Period Simulation Determined

** Water Age Analysis Determined




Figure 6.1

**Town of Addison
Capital Improvements Plan Map**





6.1 Cost Estimates

A breakdown of the unit prices used to estimate costs can be seen below in **Table 6.2 – Estimated Water System Construction Unit Prices**. Initial cost estimates and unit prices are based on current (2015) pricing assumptions with thought given to proper estimation for given project size, pavement repair, design cost, traffic control requirements, mobilization, and other items that affect project delivery. At the request of Addison, one (1) to five (5) year period cost projections have been developed using an Inflation Rate of 4.0% in accordance with Dallas/Fort Worth Metroplex average inflation. A summary of cost estimates for each project can be seen in the CIP Priority Matrix table in **Appendix G**.

Table 6.2 – Estimated Water System Construction Unit Prices

ITEM DESCRIPTION	UNIT	UNIT PRICE
Pavement Repair (6' Wide Arterial)	LF	\$ 80.00
6" PVC WL & Appurtenances	LF	\$ 66.00
6" DI WL & Appurtenances	LF	\$ 150.00
8" PVC WL & Appurtenances	LF	\$ 100.00
8" DI WL & Appurtenances	LF	\$ 131.00
10" PVC WL & Appurtenances	LF	\$ 125.00
10" DI WL & Appurtenances	LF	\$ 175.00
12" PVC WL & Appurtenances	LF	\$ 108.00
12" DI WL & Appurtenances	LF	\$ 181.00
16" PVC WL & Appurtenances	LF	\$ 142.00
16" DI WL & Appurtenances	LF	\$ 159.00
24" RCCP WL & Appurtenances	LF	\$ 313.00



Due to the nature of the CIP options being of only generally located and not designed in detail, the prepared cost estimates are conservative: the unit prices err on the side of higher rather than lower, and a 40% cost estimate contingency and a 20% Engineering, Surveying, PM & Inspection, and Geotech contingency were assumed. Budget verification should occur after 25%, 50% and 75% plan preparation phases to allow for budget updates as the potential design elements are completed. This should allow the Town of Addison to properly estimate pricing and any needed budget adjustments, as each project moves forward.

6.2 Risk-Based Analysis

To create consistency in Addison evaluating infrastructure, a method developed by Kleinfelder, Inc. to evaluate Addison's storage tanks was used as the go-by/template for the development of the Risk-Based Analysis of the water distribution system capital improvement projects. The main means of evaluating the priority order of the CIP options was a method in which Consequences of Failure (CoF) scores and Likelihood of Failure (LoF) scores were developed for each project. The consequence of failure value is, as it sounds, a metric for measuring the impact that a particular water infrastructure component failure would have if an improvement project were not implemented. The likelihood of failure value is a metric used to measure the potential/probable failure of any given water infrastructure component. For each value, a list of evaluation criteria and sub-criteria were developed in order to quantify a CoF and LoF score for each particular project. The criteria were weighted based on their perceived level of importance as determined by discussion with Addison and based upon engineering judgement. The criteria were weighted on a 1-10 scale with 10 being the most important. The criteria and weighting used as the basis for calculating the CoF and LoF scores can be seen in **Tables 6.3 and 6.4** below.



Table 6.3 – Consequence of Failure (CoF) Criteria Weightings

Criteria	Weight
Health/Environmental (Water Quality)	10
Hydrants out of Service or Hydraulically Hindered	10
Meters out of Service	8
Loss of Business	8
How Often Maintenance is Required	7
Re-Construction Timeline	4
Temporary Service Availability	6
Location of Failure	2

Table 6.4 – Likelihood of Failure (LoF) Criteria Weightings

Criteria	Weight
Age of Infrastructure	10
Pipe Material	9
Known Leakage Issues	9
Hydraulic Criteria	5
Looping Redundancy	5

Each criteria was, also, given sub-criteria as the means of quantitatively evaluating each water infrastructure improvement project. The sub-criteria were ranked on a 1-5 scale with 5 being the most critical. As a means of elucidation, an example of what the sub-criteria look like, the following is presented herein.

Table 6.5 – Likelihood of Failure Sub-Criteria for Rating Pipe Material Example

Pipe Material	
Weight: 9	
Material	Rating
CI	5
Unk	4
DI	3
PCCP	2
Steel	1
PVC	0



Assumptions were made regarding the importance of each sub-criteria using engineering judgement. For instance in the case of pipe material, as can be seen above, CI was deemed to be of the greatest likelihood of failure because of its higher potential for corrosion. The other material ratings were based mainly on this logic. Each project was then given a rating for the pipe material sub-criteria based on the material of the existing pipe. This process was repeated for each criteria for each identified project. Then, to determine the CoF or LoF score, the criteria weight was multiplied by the criteria rating determined from the sub-criteria.

Equation: $\text{CoF (or LoF)} = \text{Sub-Criteria Rating} \times \text{Criteria Weight}$

Each project's overall CoF or LoF score was determined by averaging all of the individual criteria scores together. The final step in evaluating each CIP option was the prioritization of the projects; this prioritization was accomplished by calculating a value termed Risk. Risk is a function of the Consequence of Failure and Likelihood of Failure.

Equation: $\text{Risk} = \text{CoF} \times \text{LoF}$

See **Table 6.6** for a breakdown by project of the CoF, LoF, Risk, and the project Priority. **Figure 6.2** depicts in graphical form what the CoF versus LoF for each evaluated project looks like.



Table 6.6 – CIP Risk, Cost, & Priority Summary

Option No.	CoF	LoF	Risk Factor	Priority	Improvement Cost Estimate (Current)
19	3.04	2.60	7.90	1	\$566,622
18	2.91	2.54	7.40	2	\$264,449
16	2.93	2.00	5.85	3	\$953,249
17	2.53	2.00	5.05	4	\$611,226
6	1.60	3.10	4.96	5	\$460,278
10	1.95	2.22	4.33	6	\$516,264
24	2.43	1.44	3.49	7*	\$292,290
23	2.43	1.26	3.06	8*	\$845,736
3	1.25	1.44	1.80	9	\$69,569
7	1.48	1.10	1.62	10	\$551,418
2	0.98	1.64	1.60	11	\$24,192
21	1.43	1.10	1.57	12	\$26,531
14	0.83	1.60	1.32	13	\$81,178
11	0.98	1.20	1.17	14	\$106,122
9	0.48	2.42	1.15	15	\$43,546
20	0.60	1.82	1.09	16	\$22,050
13	0.80	1.30	1.04	17	\$27,216
8	1.98	0.50	0.99	18	\$429,559
15	0.53	1.60	0.84	19	\$50,282
4	0.78	0.90	0.70	20	\$25,734
25	0.55	1.00	0.55	21**	\$238,341
22	0.75	0.70	0.53	22	\$18,950
26	0.53	0.70	0.37	23**	\$298,972
12	0.48	0.70	0.33	24	\$341,460
5	0.25	1.00	0.25	25	\$105,840
1	0.85	0.20	0.17	26	\$821,486


* Extended Period Simulation Determined

** Water Age Analysis Determined

As you can see in **Table 6.6**, the CIP cost estimate does not have any bearing on the recommended project priority. The recommended project priority is solely a function of the Risk Factor; however, it should be noted that the order in which the projects are constructed is truly at the discretion of Addison. To help facilitate and justify other project prioritizations, a detailed breakdown of the criteria and sub-criteria ratings and calculation of the CoF and LoF scores for each capital improvement project can be found in **Appendix H**.



Figure 6.2 – Risk-Based Analysis Graphical Depiction



6.3 Impact Fee Analysis

In line with the scope of work lined out in the initial contract with Addison, a simple impact fee analysis has been performed to gauge the efficacy of the proposed impact fee schedule. The proposed impact fee schedule can be seen in **Appendix I**. A general, high-level comparison of Addison’s impact fees to sixteen (16) other cities in the DFW metroplex, ranging in size from as small as the Town of Prosper to as large as the City of Fort Worth, has been conducted to prepare a statistical summary of where the Town of Addison’s proposed impact fees fall on the scale in comparison to impact fees in other cities. A summary of this statistical analysis can be seen below.



Table 6.7 – Impact Fee Comparison Summary

		Size	Addison	Minimum	Average	Maximum
Domestic Water Connection (based on meter size)*	Simple (Positive Displ.)	5/8 Inch	-	\$25.00	\$1,393.70	\$3,617.00
		3/4 Inch	\$300.00	\$28.00	\$1,842.51	\$5,425.00
		1 Inch	\$400.00	\$35.00	\$3,176.97	\$9,042.00
		1.5 Inch	\$850.00	\$45.00	\$6,776.89	\$18,085.00
	Turbine/Compound	2 Inch	\$900.00	\$73.00	\$13,692.76	\$28,936.00
		3 Inch	\$1,500.00	\$275.00	\$30,729.59	\$60,235.00
		4 Inch	\$2,000.00	\$350.00	\$55,401.65	\$111,865.00
		6 Inch	\$4,000.00	\$525.00	\$119,301.61	\$240,940.00
		8 Inch	\$5,000.00	\$725.00	\$191,305.97	\$413,040.00
		10 Inch	\$6,000.00	\$10,884.00	\$229,382.65	\$602,350.00
		12 Inch	\$8,000.00	\$451,995.00	\$451,995.00	\$451,995.00

Due to the wide variance in impact fees from city to city and the lack of previous impact fee collection data from within the Town of Addison, no specific recommendations will be made regarding the efficacy of Addison’s proposed impact fee schedule; however, the information provided should help to serve as a basis of information for the Town staff to perform a more thorough evaluation of the proposed fees. Although, a general recommendation is not to update/modify the proposed impact fees for a few years to allow time in order to evaluate the effectiveness of the fees. For Addison’s benefit, a collection of the data and research acquired for the impact fee analysis can be found in **Appendix J**.



7.0 CONCLUSION AND FUTURE CONSIDERATIONS

In conclusion, the recommendations and deliverables provided within this report are based upon sound engineering and modeling principles. However, while comprehensive, they are not all-inclusive of the many layers of intricacy present within Addison's water distribution system and at this point are at best a fair assessment and representation of the water infrastructure assets at this time. Even though Addison's distribution system is robust and the mapping, water model, capital improvement projects plan, and water master plan report provide a comprehensive evaluation of the system, there is always room for continual improvement. Wrapped up within these future considerations is the recommendation that the Water Master Plan report developed herein be updated regularly (minimum annually) to accommodate for any changes, variations, or new infrastructure development made to the water distribution system. As Addison is probably already aware, the Water-Energy Nexus is a newer field of study and evaluation that has recently become a hot topic of discussion amongst the water industry. Just as with water, energy management and efficiency is of greater importance now than ever before. Something to consider for the future enhancement of Addison's water distribution is an analysis of the pump station's energy consumption. The capabilities of the water model developed in junction with this report provide the ability to simulate energy consumption and link it to costs of energy usage. An energy audit of the pump stations has the potential to reveal ways of being more energy efficient while at the same reducing costs. A general recommendation to run pumps, as much as possible, during off-peak electricity hours could lead to energy and money savings. As an added cherry on top of the work performed on this project, below are a list of tools/training workshops that could be beneficial for Addison in relation to the Water-Energy Nexus.

- Electric Power Research Institute (EPRI)
- TRWD – Continuous Pump Energy Consumption Workshop & Training
- EPA Energy Use Assessment Tool
- Pumping System Assessment Tool – US Department of Energy



APPENDICES

Appendix A – Emergency Interconnection Record Drawings

Appendix B – Pump Station Layouts

Appendix C – Pump Curves

Appendix D – Detailed Fire Flow Test Location Maps

Appendix E – Proposed Operational Control Setting Parameters

Appendix F – Chlorine Residuals (Jan. - Sept. 2015)

Appendix G – CIP Plan Priority Matrix

Appendix H – Risk Based Analysis Calculations & Data

Appendix I – Proposed Impact Fee Schedule

Appendix J – Impact Fee Analysis Calculations & Data



Appendix A
Emergency Interconnection Record Drawings




DWU Emergency Interconnection:
Northeast Corner of Addison Road & Belt Line Road
Approximate Address: 4801 Belt Line Rd, Addison, TX 75254



DWU Emergency Interconnection:
Northeast Corner of Dallas Parkway & Westgrove Road
Approximate Address: 950 Westgrove Dr, Dallas, TX 75248

For Exhibit Purposes Only - Not to Scale



425.60'	435.60'	N 00°13'00"W	199.50'
S 89°47'00"W			
N 89°47'00"E	435.60'	N 00°13'00"W	199.50'
425.60'			
426.69'	436.69'	S 89°47'00"W	
N 89°47'00"E	436.69'	N 00°13'00"W	199.50'
426.69'			
N 89°47'00"E	436.69'	N 00°13'00"W	199.50'
426.69'			

MATCH LINE PLATE NO.

CHORD BEARING		CHORD DISTANCE		CURVE DATA			
CHORD BEARING	CHORD DISTANCE	RADIUS	CENTRAL ANGLE	ARC	TAN		
0°00'00" E	27.00'	424.26'	90°00'00"	421.24'	300.00'		
0°00'00" E	27.00'	775.00'	42°43'32"	571.16'	299.25'		
0°00'00" E	27.00'	380.00'	42°43'32"	304.66'	149.62'		
0°00'00" E	27.00'	250.00'	42°43'32"	209.50'	109.74'		
0°00'00" E	27.00'	213.00'	42°43'32"	180.98'	89.36'		
0°00'00" E	27.00'	743.00'	42°43'32"	547.55'	286.89'		
0°00'00" E	27.00'	332.00'	42°43'32"	312.00'	156.00'		
0°00'00" E	27.00'	263.00'	90°00'00"	263.00'	263.00'		
0°00'00" E	27.00'	880.00'	40°43'32"	694.78'	311.61'		
0°00'00" E	27.00'	1400.00'	30°43'32"	1251.22'	384.67'		

Note
 All materials and construction to City of Addison
 Fire plugs to be Mueller Centurion
 PVC water main to be SDR-18

As BUILT
 6/25/82
 BENT TREE TOWER NO 2
 FERGUSON-DEBRE INC
 CONSULTING ENGINEERS
 9817 KINGSLEY RD
 DALLAS TX
 OCTOBER 1980

Rev. 4 Dec. 1980 B21
 Rev. 22 Nov 80

WATER & SEWER PLANS
BENT TREE OAKS

ADDISON, DALLAS COUNTY, TEXAS
 THREADGILL-DOWDEY and ASSOCIATES
 CONSULTING ENGINEERS DALLAS, TEXAS

DESIGN	DRAWN	CHECKED	DATE	SCALE	JOB	SHEET
M.R.K.	M.R.K.	D.M.D.	JUNE, 76	1"=100'	8014	1



DWU Emergency Interconnection:
Celestial Road directly north of the Celestial PS
Approximate Address: 5501 Celestial Rd, Addison, TX 75254

For Exhibit Purposes Only - Not to Scale


NOTE:

- Contractor Shall Determine The Exact Location And Depth Of The Underground Utilities Shown Prior To Construction By Contacting The Utility Companies. The Utility Elevations Shown Are Only Approximate.
- Contractor Shall Be Responsible For Any Utility Damages Resulting From Construction.
- Contractor Shall Repair Or Replace Any Damaged Utility Equal To Or Better Than The Original Condition At No Additional Compensation.

CONSTRUCTION NOTES:

(STA. 55+42 to 61+51 See Typ. Detail Sht.)


- The following notes correspond by station number with the appropriate typical detail drawing.
- Excavate As Required To Construct The Water Line With Appurtenances, As Shown With The Typical Detail Drawing.
 - Replace With "Fit" Material To Match Existing Grades, As Shown With Typical Detail Drawing, Not A Separate Pay Item Include In Pay Item No. 101.2




NOTE:

Block All Bends, Tees And Plugs As Required By Appurtenances. See Typical Detail Sheet.

B.M. "□" Plus Mark #20 At Sta. 56+79+ On Celestial Rd. Elev. 607.32




61+00 Changed Pipe Sizes From 36" to 24", 27" to 24", Added 12" Tie-in. Changed Misc. Appurtenances		61+51	1-31-85
No.	Revision	By	Date
TOWN OF ADDISON DALLAS COUNTY, TEXAS CROSTOWN WATER LINE			
STA. 55+42 to 61+51			
GINN, INC. Consulting Engineers Dallas, Texas			
Designed - MP	Drawn - GAP	Date - NOVEMBER, 1984	Job No. - 216
Approved - HWG	Checked - GF	Scale - 1"=20'H/1"=5'V	Sheet 11 OF 20



Celestial Rd.


For Exhibit Purposes Only - Not to Scale






**DWU Emergency Interconnection:
East of the Southeast corner of Dallas Parkway &
Beltline Road
Approximate Address: 5201 Montfort Dr, Addison, TX 75254**

For Exhibit Purposes Only - Not to Scale



- NOTES:
- SEE SHEET 12 FOR PAVEMENT AND SIDEWALK SAWCUT, REMOVAL AND REPLACEMENT DETAILS.
 - LOCATION OF ALL UNDERGROUND UTILITIES ARE APPROXIMATE ONLY. REFER TO GENERAL NOTE NO. 2 ON SHEET 2.
 - CONCRETE PAVEMENT REMOVAL LIMITS SHOWN FOR INSTALLATION OF PROJECT IMPROVEMENTS ARE MAXIMUM PAYMENT LIMITS UNLESS THE CONTRACTOR IS DIRECTED OTHERWISE BY THE TOWN OF ADDISON. CONTRACTOR MAY ELECT TO REMOVE LESS PAVEMENT.
 - CONTRACTOR SHALL IDENTIFY THE PROPOSED PAVEMENT REMOVAL LIMITS IN THE FIELD, AND OBTAIN APPROVAL FOR SAME FROM THE TOWN OF ADDISON, PRIOR TO ANY PAVEMENT REMOVAL.
 - CONTRACTOR SHALL REPAIR OR REPLACE AS DIRECTED BY THE TOWN OF ADDISON ANY IRRIGATION SYSTEM OR LANDSCAPE IMPROVEMENTS AFFECTED BY OR DAMAGED DURING CONSTRUCTION. (NO SEPARATE PAY ITEM)
 - CONTRACTOR SHALL RESTORE ANY GRASSED AREAS AFFECTED BY THE CONSTRUCTION WITH LIKE MATERIALS. SOD IS REQUIRED IN AREAS OF ESTABLISHED LAWNS UNLESS APPROVED BY THE TOWN OF ADDISON. (NO SEPARATE PAY ITEM)
 - PROPOSED PIPE LENGTHS SHOWN ARE APPROXIMATE ONLY. CONTRACTOR SHALL FIELD VERIFY REQUIRED LENGTHS.
 - CONTRACTOR SHALL CONTACT DALLAS WATER UTILITIES DISTRIBUTION AT (214) 670-7851 TO ARRANGE FOR VALVE CLOSURE AND DRAINING OF 54" WATER LINE.
 - CONTRACTOR SHALL ONLY CLOSE ONE LANE OF TRAFFIC ON BELT LINE ROAD FROM 9:30 A.M. TO 3:30 P.M.



REVISED NOTES AND ADDED DIMENSIONS		B.G. 5/17/94	
No.	Revision	By	Date
1			

TOWN OF ADDISON
DALLAS COUNTY, TEXAS
WATER MAIN IMPROVEMENTS
BELT LINE ROAD AT SAKOWITZ DRIVE
DISCONNECT NO. 7

Espy, Hutton & Associates, Inc.
ENGINEERING & ENVIRONMENTAL CONSULTANTS

Designed - MR Drawn - EH/AA Date - MARCH, 1984 Job No. 18225
Approved - BG Checked - BG Scale - 1"=40'H, 1"=8'V Sheet 9 OF 13






Appendix B Pump Station Layouts



Surveyor Pump Station Layout



Celestial Pump Station Layout




Pump # 1 Pump #2 Pump #3 Pump #4 Pump #5

LIMIT LINE OF EXCAVATED AREA REQUIRING CRUSHED STONE BACKFILL

Sidewalk curb eliminated and made part of drive

Added Thrust Block


Added Thrust Block




2 SECTION
1/2" = 1'-0"

PIPING PLAN
1/8" = 1'-0"


- NOTE:
- FOR STRUCTURAL DETAILS OF PIPE CHANNEL SEE SHT. S-5
 - PS DENOTES PIPE SUPPORT
 - SEE A-1 FOR BUILDING DIMENSIONS
 - CHLORINE ROOM SHALL BE PIPED FOR FUTURE CHLORINE EQUIPMENT. EXTEND PIPE MIN. 2' ABOVE FLOOR



PIPE SUPPORT - 30" PIPE
NTS



PIPE SUPPORT - 20" PIPE
NTS



1 SECTION
1/4" = 1'-0"

597 HJL
574.42 FF
GSA
HJL = W202

No.	Revision	By	Date
TOWN OF ADDISON DALLAS COUNTY, TEXAS			
CELESTIAL ROAD PUMP STATION			
PIPING PLAN			
GINN, INC.			
Consulting Engineers Dallas, Texas			
Designed - RCH	Drawn - GAP	Date - JAN, 1987	Job No. - 217

Randall C. Held



Appendix C Pump Curves



Celestial Pump Station: Pump Curves 1, 3, & 5



Celestial Pump Station: Pump Curve 2

Company: Jersey Equipment Co.
 Name: Malcolm Murphy
 Date: 4/7/2015

Addison Celestial #2




Pump:
 Size: SG16S (2 stage)
 Type: VERTTURBINE
 Synch speed: 1800 rpm
 Curve:
 Specific Speeds:
 Dimensions:
 Vertical Turbine:
 Speed: 1770 rpm
 Dia: 12.95 in
 Impeller:
 Ns: 3501
 Nss: 10296
 Suction: 12 in
 Discharge: 12 in
 Bowl size: 16 in
 Max lateral: 1.19 in
 Thrust K factor: ---

Search Criteria:
 Flow: 3200 US gpm
 Head: 190 ft
Fluid:
 Water
 SG: 1
 Viscosity: 1.105 cP
 NPSHa: ---
 Temperature: 60 °F
 Vapor pressure: 0.2563 psi a
 Atm pressure: 14.7 psi a
Motor:
 Standard: US
 Enclosure: TYPE_1
 Sizing criteria: Max Power on Design Curve
 Size: 200 hp
 Speed: 1800
 Frame: ---



Pump Limits:
 Temperature: ---
 Pressure: ---
 Sphere size: 1.187 in
 Power: ---
 Eye area: 78.4 in²

--- Data Point ---	
Flow:	3200 US gpm
Head:	190 ft
Eff:	83.1%
Power:	185 hp
NPSHr:	18.7 ft
--- Design Curve ---	
Shutoff head:	308 ft
Shutoff dP:	133 psi
Min flow:	---
BEP:	84.1% @ 3560 US gpm
NOL power:	187 hp @ 3560 US gpm
--- Max Curve ---	
Max power:	215 hp @ 3708 US gpm



Discharge size also available in 14". Suction size is bell.

Performance Evaluation:						
Flow US gpm	Speed rpm	Head ft	Efficiency %	Power hp	NPSHr ft	
3840	1770	160	83.5	185	24	
3200	1770	190	83.1	185	18.7	
2560	1770	214	76.3	181	14.5	
1920	1770	236	64.4	178	13	
1280	1770	---	---	---	---	



DISCHARGE FLANGE
14" #150 ANSI RF

MOTOR

MAKE U. S. Motors
ENCLOSURE WP-1
N.R.R. or S.R.G.
H.P. 200 S.F. 1.15
R.P.M. 1800
PHASE 3 CYCLE 60
VOLTAGE 460
V.H.S. or V.S.S.
premium efficiency
ground lug
120V heaters
class F insulation
class B rise
PTC thermistors
25 year average bearing life
short commercial motor test

DATE 2/27/98
DISTRIBUTOR Jersey Equipment

JOB Celestial Pump Station - Addison, TX
Pump #2

JOB/QUOTE # _____
QUANTITY one

G.P.M. 3200
T.D.H. 190'
STRAINER TYPE clip-on basket strainer
galvanized
BOWL MODEL # SG16S-2

COLUMN ASSY. 1-11/16"Ø x 14"Ø
flanged product lube column assembly with
416 S. S. lineshaft and couplings; 316 S. S.
bolting; .375" wall pipe

FOUNDATION PLATE not specified

DISCHARGE HEAD F-800M
fabricated steel

SEAL TYPE Durametallic mechanical seal

IMP. DIA. 12.969"Ø±
IMP. TYPE semi-open
SPECIAL belled suction; 316 S. S. collets and
316 S. S. bolting; bronze bearings

OTHER testing and coating as noted in points
of interest; Size 4 spacer type motor coupling



Celestial Pump Station: Pump Curve 4

Company: Jersey Equipment Co.
 Name: Malcolm Murphy
 Date: 4/7/2015

Addison Celestial #4



Pump:

Size: SJ14C (3 stage)
 Type: VERTTURBINE
 Synch speed: 1800 rpm
 Curve:
 Specific Speeds:
 Dimensions:
 Vertical Turbine:
 Speed: 1770 rpm
 Dia: 10.78 in
 Impeller:
 Ns: 3057
 Nss: 9164
 Suction: 10 in
 Discharge: 10 in
 Bowl size: 14 in
 Max lateral: 1 in
 Thrust K factor: ---

Search Criteria:

Flow: 2000 US gpm Head: 190 ft

Fluid:

Water
 SG: 1
 Viscosity: 1.105 cP
 NPSHa: ---
 Temperature: 60 °F
 Vapor pressure: 0.2563 psi a
 Alm pressure: 14.7 psi a


Motor:

Standard: US
 Enclosure: TYPE_1
 Sizing criteria: Max Power on Design Curve
 Size: 125 hp
 Speed: 1800
 Frame: ---

Pump Limits:

Temperature: ---
 Pressure: ---
 Sphere size: 1.312 in
 Power: ---
 Eye area: 48.2 in²

--- Data Point ---	
Flow:	2000 US gpm
Head:	190 ft
Eff:	84.2%
Power:	113 hp
NPSHr:	16.4 ft
--- Design Curve ---	
Shutoff head:	336 ft
Shutoff dP:	145 psi
Min flow:	---
BEP:	84.5% @ 1942 US gpm
NOL power:	115 hp @ 2199 US gpm
--- Max Curve ---	
Max power:	168 hp @ 2255 US gpm



Performance Evaluation:

Flow US gpm	Speed rpm	Head ft	Efficiency %	Power hp	NPSHr ft
2400	1770	148	79.2	113	21
2000	1770	190	84.2	113	16.4
1600	1770	220	80.8	110	12.3
1200	1770	---	---	---	---
800	1770	---	---	---	---

DATE 2/27/98
DISTRIBUTOR Jersey Equipment

JOB Celestial Pump Station - Addison, TX
Pump #4

JOB/QUOTE # _____
QUANTITY one

G.P.M. 2000
T.D.H. 190'
STRAINER TYPE clip-on basket strainer
galvanized

BOWL MODEL # SJ14C-2

COLUMN ASSY. 1-1/2"Ø X 12"
flanged product lube column assembly with
416 S. S. lineshaft and couplings; 316 S. S.
bolting; .375" wall pipe

FOUNDATION PLATE not specified



DISCHARGE HEAD F-600M
fabricated steel

SEAL TYPE Durametallic mechanical seal

IMP. DIA. 11.500"Ø±
IMP. TYPE enclosed

SPECIAL bellied suction; 316 S. S. coflets and
bolting; bronze bearings

OTHER testing and coating as noted in points
interest; Size 3 spacer type motor coupling



DISCHARGE FLANGE
12" #150 ANSI RF

MOTOR

MAKE U. S. Motors
ENCLOSURE WP-1
N.R.R. or S.R.G. _____
H.P. 125 S.F. 1.15
R.P.M. 1800
PHASE 3 CYCLE 60
VOLTAGE 460
V.H.S. or V.S.S. _____

premium efficiency
ground lug
120V heaters
class F insulation
class B rise
PTC thermistors
25 year average bearing life
short commercial motor test




Surveyor Pump Station: Pump Curve 1

* Pump #1

5-5-76 E-7854

Curves show approximately the characteristics when pumping clear water with specific gravity of 1.0. No guarantee is made except for the rated point.





Surveyor Pump Station: Pump Curves 2 & 3

* Pump #2:3

AXIALLY-SPLIT PUMPS
9000-Series Single-Stage, Double Suction Pumps
with Mechanical Seals or Packing
Performance Curves — 1770 Rpm





CP 3

Page 53

June, 1984

Supersedes all previous issues



SELECTION AND CURVES



Appendix D
Detailed Fire Flow Test Request Package



TOWN OF ADDISON

FIRE FLOW TEST REQUEST MAPS



Prepared By:

BURY

Town of Addison - Fire Flow Test Request Map

Map Disclaimer

These maps are only for graphic display and general planning purposes. The information contained herein is deemed reliable, but is not guaranteed. Inquiries concerning information displayed on these maps, their sources, and intended uses should be directed to:

Town of Addison
 C/O: Jacob Niemeier
 BURY, Inc.
 (972) 991-0011

The system maps are supplied on an "as is, where is" basis. The Town of Addison assumes no obligation or liability for the use of system maps by any person and makes no representations or promises regarding the completeness or accuracy of the maps or their fitness for a particular purpose.

Data Creation

Information displayed on these maps was derived from multiple sources. Features were created from existing GIS information publicly available, and from field-collected GPS data.

Use of Data

Individuals or companies may use maps prepared by the Town of Addison and may reproduce the information herein for internal use upon approval by the Town of Addison. Requests to reproduce copies of maps or data must be submitted in writing to the Town of Addison with an explanation of the intended use. An individual or company may not reproduce any map or product prepared by the Town of Addison with the intent of selling these maps or products for profit.

Data Originator

Bury, Inc. compiled and prepared these maps under contract with the Town of Addison. Inquiries regarding the map source data should be submitted to the Town of Addison.

Legend


-  Addison Town Limits
-  Addison Parcels
-  Pipe Crossing (No Connection)

Fire Hydrant


-  Flow Hydrant
-  Residual Hydrant

Water Line

-  Addison
-  Carrollton
-  DWU
-  NTTA
-  Private
-  Farmers Branch (Abandoned)



Test Location No. 1



Fire Flow Test Data

Date: 5-4-15 Time: 9:06 am

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) 16.42
 Celestial GST Elevation (ft) 13.11

Surveyor EST Elevation (ft) 23.3
 Addison Circle EST Elevation (ft) OFFLINE

Surveyor Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 2735.40 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm


Celestial Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 0.0.5, gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm
 Pump 4: On or Off ; If On, Flow = 2999.70 gpm
 Pump 5: On or Off ; If On, Flow = 0 gpm

Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1
 Static Pressure = 39 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 36 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 40 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 38 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 1 ft
 Pitot Pressure = 18 psi
 Flow = 717 gpm



Test Location No. 2



Fire Flow Test Data

Date: 06/04/15 Time: 10:05 am

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) <u>12.87</u>	Surveyor EST Elevation (ft) <u>27.15</u>
Celestial GST Elevation (ft) <u>14.20</u>	Addison Circle EST Elevation (ft) <u>offline</u>
Surveyor Pump Station Conditions	Celestial Pump Station Conditions
Pump 1: On or Off ; If On, Flow = <u>Ø</u> gpm	Pump 1: On or Off ; If On, Flow = <u>Ø</u> gpm
Pump 2: On or Off ; If On, Flow = <u>Ø</u> gpm	Pump 2: On or Off ; If On, Flow = <u>Ø</u> gpm
Pump 3: On or Off ; If On, Flow = <u>2648.7</u> gpm	Pump 3: On or Off ; If On, Flow = <u>Ø</u> gpm
	Pump 4: On or Off ; If On, Flow = <u>2968.6</u> gpm
	Pump 5: On or Off ; If On, Flow = <u>Ø</u> gpm

Fire Flow Test Results


RESIDUAL Fire Hydrant No. 1	RESIDUAL Fire Hydrant No. 2	FLOW Fire Hydrant
Static Pressure = <u>60</u> psi	Static Pressure = <u>57</u> psi	Gauge Distance From Hydrant Top Nut = <u>1</u> ft
Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Pitot Pressure = <u>27</u> psi
Residual Pressure = <u>57</u> psi	Residual Pressure = <u>54</u> psi	Flow = <u>878</u> gpm

0 100 200 400 Feet



BURY

Test Location No. 3



Fire Flow Test Data

Date: 5-4-15 Time: 10:52 am

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) <u>13.65</u>	Surveyor EST Elevation (ft) <u>27.9</u>
Celestial GST Elevation (ft) <u>12.35</u>	Addison Circle EST Elevation (ft) <u>OFF LINE</u>
Surveyor Pump Station Conditions	Celestial Pump Station Conditions
Pump 1: On or Off ; If On, Flow = <u>0</u> gpm	Pump 1: On or Off ; If On, Flow = <u>0</u> gpm
Pump 2: On or Off ; If On, Flow = <u>2635.27</u> gpm	Pump 2: On or Off ; If On, Flow = <u>0.05</u> gpm
Pump 3: On or Off ; If On, Flow = <u>0</u> gpm	Pump 3: On or Off ; If On, Flow = <u>0</u> gpm
	Pump 4: On or Off ; If On, Flow = <u>2954.5</u> gpm
	Pump 5: On or Off ; If On, Flow = <u>0</u> gpm

Fire Flow Test Results


RESIDUAL Fire Hydrant No. 1	RESIDUAL Fire Hydrant No. 2	FLOW Fire Hydrant
Static Pressure = <u>50</u> psi	Static Pressure = <u>49</u> psi	Gauge Distance From Hydrant Top Nut = <u>1</u> ft
Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Pitot Pressure = <u>25</u> psi
Residual Pressure = <u>48</u> psi	Residual Pressure = <u>46</u> psi	Flow = <u>845</u> gpm

0 100 200 400 Feet



BURY

Test Location No. 4



Fire Flow Test Data


Date: 6/11/15 Time: 1:57 pm

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) <u>10.24</u>	Surveyor EST Elevation (ft) <u>224</u>
Celestial GST Elevation (ft) <u>22.21</u>	Addison Circle EST Elevation (ft) <u>OFF LINE</u>
Surveyor Pump Station Conditions	Celestial Pump Station Conditions
Pump 1: On or Off ; If On, Flow = <u>OFF</u> gpm	Pump 1: On or Off ; If On, Flow = <u>OFF</u> gpm
Pump 2: On or Off ; If On, Flow = <u>OFF</u> gpm	Pump 2: On or Off ; If On, Flow = <u>OFF</u> gpm
Pump 3: On or Off ; If On, Flow = <u>OFF</u> gpm	Pump 3: On or Off ; If On, Flow = <u>OFF</u> gpm
	Pump 4: On or Off ; If On, Flow = <u>OFF</u> gpm
	Pump 5: On or Off ; If On, Flow = <u>OFF</u> gpm

Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1	RESIDUAL Fire Hydrant No. 2	FLOW Fire Hydrant
Static Pressure = <u>48</u> psi	Static Pressure = <u>56</u> psi	Gauge Distance From Hydrant Top Nut = <u>1.5</u> ft
Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Gauge Distance From Hydrant Top Nut = <u>10</u> ft	Pitot Pressure = <u>28</u> psi
Residual Pressure = <u>46</u> psi	Residual Pressure = <u>56</u> psi	Flow = <u>894</u> gpm



Test Location No. 5



Fire Flow Test Data

Date: 5-4-15 Time: 10:04 am

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) 14.96
 Celestial GST Elevation (ft) 12.69

Surveyor EST Elevation (ft) 25.8
 Addison Circle EST Elevation (ft) OFF LINE

Surveyor Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 2668.08 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm


Celestial Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 0.05 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm
 Pump 4: On or Off ; If On, Flow = 2946.30 gpm
 Pump 5: On or Off ; If On, Flow = 0 gpm

Fire Flow Test Results


RESIDUAL Fire Hydrant No. 1
 Static Pressure = 58 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 56 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 56 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 54 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 1 ft
 Pitot Pressure = 32 psi
 Flow = 956 gpm



Test Location No. 6



Fire Flow Test Data

Date: 6/11/15 Time: 2:26 pm

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) 10.96
 Celestial GST Elevation (ft) 22.30

Surveyor EST Elevation (ft) 21.5
 Addison Circle EST Elevation (ft) OFF LINE

Surveyor Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = OFF gpm
 Pump 2: On or Off ; If On, Flow = OFF gpm
 Pump 3: On or Off ; If On, Flow = OFF gpm


Celestial Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = OFF gpm
 Pump 2: On or Off ; If On, Flow = 3668.0 gpm
 Pump 3: On or Off ; If On, Flow = OFF gpm
 Pump 4: On or Off ; If On, Flow = OFF gpm
 Pump 5: On or Off ; If On, Flow = OFF gpm

Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1
 Static Pressure = 76 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 76 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 74 psi
 Gauge Distance From Hydrant Top Nut = 0.5 ft
 Residual Pressure = 74 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 3 ft
 Pitot Pressure = 45 psi
 Flow = 1133 gpm



Test Location No. 7



Fire Flow Test Data

Date: 5-4-15 Time: 1:17 pm

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) 10.04
 Celestial GST Elevation (ft) 14.32

Surveyor EST Elevation (ft) 34.0
 Addison Circle EST Elevation (ft) OFF LINE

Surveyor Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 2379.07 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm


Celestial Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 0.0.51 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm
 Pump 4: On or Off ; If On, Flow = 0 gpm
 Pump 5: On or Off ; If On, Flow = 0 gpm

Fire Flow Test Results


RESIDUAL Fire Hydrant No. 1
 Static Pressure = 60 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 58 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 58 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 56 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 1 ft
 Pitot Pressure = 32 psi
 Flow = 970 gpm



Test Location No. 8



Fire Flow Test Data

Date: 5-4-15 Time: 1:35 pm

Boundary Conditions at Time of Test


Surveyor GST Elevation (ft) <u>9.66</u>	Surveyor EST Elevation (ft) <u>34.0</u>
Celestial GST Elevation (ft) <u>14.32</u>	Addison Circle EST Elevation (ft) <u>OFF LINE</u>
Surveyor Pump Station Conditions	Celestial Pump Station Conditions
Pump 1: On or Off ; If On, Flow = <u>0</u> gpm	Pump 1: On or Off ; If On, Flow = <u>0</u> gpm
Pump 2: On or Off ; If On, Flow = <u>2321.90</u> gpm	Pump 2: On or Off ; If On, Flow = <u>0.0.5.</u> gpm
Pump 3: On or Off ; If On, Flow = <u>0</u> gpm	Pump 3: On or Off ; If On, Flow = <u>0</u> gpm
	Pump 4: On or Off ; If On, Flow = <u>0</u> gpm
	Pump 5: On or Off ; If On, Flow = <u>0</u> gpm

Fire Flow Test Results


RESIDUAL Fire Hydrant No. 1
 Static Pressure = 84 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 82 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 86 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 78 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 1 ft
 Pitot Pressure = 32 psi
 Flow = 956 gpm



Test Location No. 8 - Residual Pressure Re-Test



Fire Flow Test Data

Date: 06/04/15 Time: 3:19pm

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) <u>22.49 9.2</u>	Surveyor EST Elevation (ft) <u>25.3</u>
Celestial GST Elevation (ft) <u>22.49</u>	Addison Circle EST Elevation (ft) <u>offline</u>
Surveyor Pump Station Conditions	Celestial Pump Station Conditions
Pump 1: On or Off ; If On, Flow = <u>∅</u> gpm	Pump 1: On or Off ; If On, Flow = <u>∅</u> gpm
Pump 2: On or Off ; If On, Flow = <u>∅</u> gpm	Pump 2: On or Off ; If On, Flow = <u>∅</u> gpm
Pump 3: On or Off ; If On, Flow = <u>∅</u> gpm	Pump 3: On or Off ; If On, Flow = <u>∅</u> gpm
	Pump 4: On or Off ; If On, Flow = <u>305.3</u> gpm
	Pump 5: On or Off ; If On, Flow = <u>∅</u> gpm


Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1	RESIDUAL Fire Hydrant No. 2	FLOW Fire Hydrant
Static Pressure = <u>80</u> psi	Static Pressure = <u>86</u> psi	Gauge Distance From Hydrant Top Nut = <u>∅</u> ft
Gauge Distance From Hydrant Top Nut = <u>∅</u> ft	Gauge Distance From Hydrant Top Nut = <u>∅</u> ft	Pitot Pressure = <u>∅</u> psi
Residual Pressure = <u>∅</u> psi	Residual Pressure = <u>∅</u> psi	Flow = <u>∅</u> gpm

** Just Residual Pressure Re-Test!*



Test Location No. 9



Fire Flow Test Data


Date: 5-4-15 Time: 2:48pm

Boundary Conditions at Time of Test


Surveyor GST Elevation (ft) <u>8.02</u>	Surveyor EST Elevation (ft) <u>33.3</u>
Celestial GST Elevation (ft) <u>16.74</u>	Addison Circle EST Elevation (ft) <u>OFF LINE</u>
Surveyor Pump Station Conditions	Celestial Pump Station Conditions
Pump 1: On or Off ; If On, Flow = <u>0</u> gpm	Pump 1: On or Off ; If On, Flow = <u>0</u> gpm
Pump 2: On or Off ; If On, Flow = <u>0</u> gpm	Pump 2: On or Off ; If On, Flow = <u>0.0.5.</u> gpm
Pump 3: On or Off ; If On, Flow = <u>0</u> gpm	Pump 3: On or Off ; If On, Flow = <u>0</u> gpm
	Pump 4: On or Off ; If On, Flow = <u>0</u> gpm
	Pump 5: On or Off ; If On, Flow = <u>0</u> gpm

Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1	RESIDUAL Fire Hydrant No. 2	FLOW Fire Hydrant
Static Pressure = <u>60</u> psi	Static Pressure = <u>60</u> psi	Gauge Distance From Hydrant Top Nut = <u>1</u> ft
Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Gauge Distance From Hydrant Top Nut = <u>1</u> ft	Pitot Pressure = <u>32</u> psi
Residual Pressure = <u>59</u> psi	Residual Pressure = <u>58</u> psi	Flow = <u>956</u> gpm



Test Location No. 10



Fire Flow Test Data

Date: 5-4-15 Time: 1:56pm

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) 9.17
 Celestial GST Elevation (ft) 15.48

Surveyor EST Elevation (ft) 33.9
 Addison Circle EST Elevation (ft) OFF LINE

Surveyor Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 2218.53 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm


Celestial Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 0.0.5. gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm
 Pump 4: On or Off ; If On, Flow = 0 gpm
 Pump 5: On or Off ; If On, Flow = 0 gpm

Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1
 Static Pressure = 60 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 58 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 58 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 56 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 1 ft
 Pitot Pressure = 30 psi
 Flow = 925 gpm



Test Location No. 11



Fire Flow Test Data

Date: 5-4-15 Time: 2:22 pm

Boundary Conditions at Time of Test

Surveyor GST Elevation (ft) 8.57
 Celestial GST Elevation (ft) 16.10

Surveyor EST Elevation (ft) 33.8
 Addison Circle EST Elevation (ft) OFF LINE

Surveyor Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 2302.93 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm

Celestial Pump Station Conditions
 Pump 1: On or Off ; If On, Flow = 0 gpm
 Pump 2: On or Off ; If On, Flow = 0.05 gpm
 Pump 3: On or Off ; If On, Flow = 0 gpm
 Pump 4: On or Off ; If On, Flow = 0 gpm
 Pump 5: On or Off ; If On, Flow = 0 gpm

Fire Flow Test Results

RESIDUAL Fire Hydrant No. 1
 Static Pressure = 88 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 84 psi

RESIDUAL Fire Hydrant No. 2
 Static Pressure = 88 psi
 Gauge Distance From Hydrant Top Nut = 1 ft
 Residual Pressure = 86 psi

FLOW Fire Hydrant
 Gauge Distance From Hydrant Top Nut = 1 ft
 Pitot Pressure = 45 psi
 Flow = 1133 gpm





Appendix E

Proposed Operational Control Setting Parameters



Operational Settings A

	Pump GPM	Pump #	Pump Rotation	Addison Circle EST Level	
				On (ft)	Off (ft)
Celestial Pump Station	7000	1, 3, or 5	Lead	18	34
	3200	2	Lead Lag	17	28
	2000	4	Lag	16	26
	7000	1, 3, or 5	Lag #2	14	24
	7000	1, 3, or 5	Lag Lag	12	22

	Pump GPM	Pump #	Pump Rotation	Pressure	
				On (psi)	Off (psi)
Surveyor Pump Station	3850	1	Manual On/Off ⁽²⁾	63	75.5
	3000	2 or 3	Manual On/Off ⁽²⁾	62	80
	3000	2 or 3	Auto ⁽¹⁾	62	80

Note:

(1) One pump is always set in auto mode and a different pump is rotated into auto mode daily.

(2) Each pump will be manually operated daily in order to perform Surveyor Ground Storage Tank turnover by draining it down to 8' daily. This GST tank drain down was approximated in the Water Model by running the pump between 8:00 am and 3:00 pm daily.

	DWU ROF Meter (MGD)	Ground Storage Tank Level		
		On (ft)	Off (ft)	
Ground Storage	Surveyor	1.2	20	21
	Celestial	9.8	16	22.8

	Storage Tank	Tank Level	
		Low (ft)	High (ft)
Alarm Settings	Addison Circle EST	16	38
	Surveyor EST	14	38
	Surveyor GST	7.5	23
	Celestial GST	12	23.5



Operational Settings B.1

	Pump GPM	Pump #	Pump Rotation	Addison Circle EST Level	
				On (ft)	Off (ft)
Celestial Pump Station	7000	1, 3, or 5	Lead	26	36
	3200	2	Lead Lag	22	25
	2000	4	Lag	16	26
	7000	1, 3, or 5	Lag #2	14	24
	7000	1, 3, or 5	Lag Lag	10	20

	Pump GPM	Pump #	Pump Rotation	Pressure	
				On (psi)	Off (psi)
Surveyor Pump Station	3850	1	Manual On/Off ⁽²⁾	63	75.5
	3000	2 or 3	Manual On/Off ⁽²⁾	62	80
	3000	2 or 3	Auto ⁽¹⁾	62	80

Note:

(1) One pump is always set in auto mode and a different pump is rotated into auto mode daily.

(2) Each pump will be manually operated daily in order to perform Surveyor Ground Storage Tank turnover by draining it down to 8' daily. This GST tank drain down was approximated in the Water Model by running the pump between 8:00 am and 3:00 pm daily.

	DWU ROF Meter (MGD)	Ground Storage Tank Level		
		On (ft)	Off (ft)	
Ground Storage	Surveyor	1.2	20	21
	Celestial	9.8	16	22.8

	Storage Tank	Tank Level	
		Low (ft)	High (ft)
Alarm Settings	Addison Circle EST	16	38
	Surveyor EST	14	38
	Surveyor GST	7.5	23
	Celestial GST	12	23.5



Operational Settings B.2

	Pump GPM	Pump #	Pump Rotation	Addison Circle EST Level	
				On (ft)	Off (ft)
Celestial Pump Station	7000	1, 3, or 5	Lead	26	36
	3200	2	Lead Lag	22	26
	2000	4	Lag	16	26
	7000	1, 3, or 5	Lag #2	14	24
	7000	1, 3, or 5	Lag Lag	10	20

	Pump GPM	Pump #	Pump Rotation	Pressure	
				On (psi)	Off (psi)
Surveyor Pump Station	3850	1	Manual On/Off ⁽²⁾	63	75.5
	3000	2 or 3	Manual On/Off ⁽²⁾	62	80
	3000	2 or 3	Auto ⁽¹⁾	62	80

Note:

(1) One pump is always set in auto mode and a different pump is rotated into auto mode daily.

(2) Each pump will be manually operated daily in order to perform Surveyor Ground Storage Tank turnover by draining it down to 8' daily. This GST tank drain down was approximated in the Water Model by running the pump between 8:00 am and 3:00 pm daily.

	DWU ROF Meter (MGD)	Ground Storage Tank Level		
		On (ft)	Off (ft)	
Ground Storage	Surveyor	1.2	20	21
	Celestial	9.8	16	22.8

	Storage Tank	Tank Level	
		Low (ft)	High (ft)
Alarm Settings	Addison Circle EST	16	38
	Surveyor EST	14	38
	Surveyor GST	7.5	23
	Celestial GST	12	23.5



Operational Settings C

	Pump GPM	Pump #	Pump Rotation	Addison Circle EST Level	
				On (ft)	Off (ft)
Celestial Pump Station	2000	2	Lead	17	25
	3200	4	Lead Lag	15	20
	7000	1, 3, or 5	Lag	12	20
	7000	1, 3, or 5	Lag #2	11	19
	7000	1, 3, or 5	Lag Lag	10	18

	Pump GPM	Pump #	Pump Rotation	Pressure	
				On (psi)	Off (psi)
Surveyor Pump Station	3850	1	Manual On/Off ⁽²⁾	63	75.5
	3000	2 or 3	Manual On/Off ⁽²⁾	62	80
	3000	2 or 3	Auto ⁽¹⁾	62	80

Note:

(1) One pump is always set in auto mode and a different pump is rotated into auto mode daily.

(2) Each pump will be manually operated daily in order to perform Surveyor Ground Storage Tank turnover by draining it down to 8' daily. This GST tank drain down was approximated in the Water Model by running the pump between 8:00 am and 3:00 pm daily.

	DWU ROF Meter (MGD)	Ground Storage Tank Level		
		On (ft)	Off (ft)	
Ground Storage	Surveyor	1.2	20	21
	Celestial	9.8	12	14.8

	Storage Tank	Tank Level	
		Low (ft)	High (ft)
Alarm Settings	Addison Circle EST	16	38
	Surveyor EST	14	38
	Surveyor GST	7.5	23
	Celestial GST	12	23.5



Appendix F
Chlorine Residuals (Jan. - Sept. 2015)







Chlorine Residual Tabular Data

	Chlorine Residuals (mg/L)																											
	CEL GSR	SUR GSR	Sur EST	2	CEL GSR	SUR GSR	Sur EST	6	CEL GSR	SUR GSR	Sur EST	11	CEL GSR	SUR GSR	Sur EST	13	CEL GSR	SUR GSR	Sur EST	14	CEL GSR	SUR GSR	Sur EST	15	CEL GSR	SUR GSR	Sur EST	23
Jan	3.47	3.04	2.98	3	3.77	1.91	3.07	2.4	3.31	3.08	3	1.5	3.75	3.95	4.2	1.1	3.52	3.71	3.02	2.9	3.43	3.4	3.03	3.1	3.59	3.72	3.79	3.3
	3.12	3.59	3.69	3.2	3.77	3.7	3.82	2.8	3.05	2.08	2.91	1.7	3.89	3.89	3	1.8	3.28	2.1	3.05	3.4	3.3	3.71	3.82	2.9	3.4	3.76	3.76	2.3
	3.35	3.68	2.87	3.1	3.17	3.52	3.61	2.7	3.52	2.04	2.87	1.9	3.06	3.64	3.73	1.6	3.37	2.62	2.9	3.5	3.39	1.95	2.85	2.7	3.19	2.08	2.75	3
	3.54	3.58	2.97	3.3	3.25	3.58	3.55	2.8	3.5	2.28	2.95	2	3.42	3.76	3.07	1.9	3.55	3.51	3.47	3.2	3.6	2.33	2.94	3	3.13	3.58	3.53	3.3
Feb	3.25	2.65	3.08	3.1	2.99	2.19	2.83	2.6	3.22	3.3	3.31	1.7	3.07	3.25	3.28	1.4	3.5	2.65	3.02	3.6	3.29	2.5	2.94	2.8	3.48	3.68	3.69	3
	3.32	3.44	3.45	3.3	3.16	3.3	3.09	2.8	3.25	3.3	3.3	1.8	3.13	2.33	2.94	1.7	3.41	3.43	3.44	3.9	3.38	3.48	3.46	3.3	3.19	3.28	3.27	2.2
	3.46	2.3	2.93	3.3	3.51	3.77	3.64	3.1	3.38	3.91	3.85	1.9	3.4	3.87	3.74	2.2	3.12	2.29	2.85	3.2	3.13	3.65	3.62	2.5	3.47	3.81	3.74	3.6
	3.61	2.68	3.28	3.1	3.66	3.94	3.82	2.9	3.54	3.65	3.4	2	3.47	3.83	3.64	1.8	3.54	3.9	3.46	3.5	3.7	2.52	3.74	2.7	3.55	3.83	3.69	3.5
Mar	3.41	3.78	3.64	3.1	3.39	2.69	3.15	2.4	3.38	3.78	3.56	1.7	3.47	3.58	3.11	1.4	3.37	3.65	3.38	3.3	3.22	3.78	3.09	3.2	3.5	3.99	3.96	3.3
	3.59	2.82	3.54	3.5	3.54	2.91	3.56	3.2	3.53	3.23	3.51	1.2	3.61	3.02	3.31	2.4	3.64	2.77	3.28	3.7	3.76	3.82	3.8	3.2	3.56	3.68	3.28	2.8
	3.79	3.01	3.66	3.2	3.65	3.55	3.78	3.7	3.67	3.22	3.56	1.6	3.67	4.04	3.83	1.7	3.89	2.73	3.28	3.2	3.83	3.83	3.7	3	3.73	3.08	3.33	3.8
	3.65	3.92	3.26	3.7	3.64	3.83	3.64	3.2	3.75	3.79	3.61	2	3.71	3.82	3.61	1.8	3.64	3.82	3.69	3.7	3.71	2.83	3.23	2.6	3.59	2.9	3.19	3.7
Apr	3.55	3.72	3.3	3.4	3.7	3.83	3.8	2.2	3.62	2.88	-	1.6	3.74	3.82	3.83	2.2	3.56	3.58	3.5	4	3.67	3.3	3.44	3.1	3.57	3.78	3.75	3.7
	3.57	3.65	3.65	3.7	3.29	2.91	3.32	3.1	3.53	2.95	3.18	2.8	3.4	3.02	3.67	1.8	3.14	3.88	3.12	3.6	3.63	3.61	3.94	3.6	3.45	3.7	3.75	3.2
	3.31	3.7	3.7	3.4	3.41	3.66	3.71	3.5	3.46	3.62	3.61	2.1	3.37	3.32	3.67	1.8	3.33	3.67	3.72	3.7	3.42	3.72	3.66	3.1	3.43	3.59	3.56	3.5
	2.55	3.75	3.76	3.1	2.64	3.58	3.71	3.1	3.22	3.55	3.56	2.4	3	3.87	3.88	2.3	2.77	3.52	3.58	3.5	2.61	3.36	3.64	3.1	2.74	3.64	3.7	3.5
May	3.02	3.17	3.48	3.2	2.56	3.78	3.84	3.3	2.73	3.13	3.77	2.4	2.27	3.78	3.95	1.4	2.79	2.8	3.29	3.8	2.17	3.73	3.86	2.6	2.48	3.62	3.55	3.82
	3.07	3.82	3.18	2.8	2.41	3.72	3.87	3.7	3.05	3.83	3.71	2.2	3.31	3.88	3.79	1.6	1.15	2.86	3.14	3.5	3.86	3.85	3.87	3	3.1	3.8	3.77	3.8
	3.33	3.94	3.84	3.1	3.44	3.89	2.98	3	2.87	3.94	3.82	1.9	3.28	4	3.86	1.3	3.51	3.93	3.87	3.3	3.63	3.41	3.17	2.8	1.66	2.91	3.28	3.5
	3.43	3.79	3.7	2.9	2.73	3.34	3.86	2.8	3.07	3.58	2.35	1.2	2.91	3.51	3.47	1.7	2.67	3.29	3.19	2.2	3.17	3.54	3.44	2	2.56	3.33	3.2	2.5
Jun	2.83	2.05	2.51	2.7	2.99	3.73	3.65	2.3	2.78	3.86	3.82	1.1	3.13	3.43	3.92	2.3	2.27	3.53	2.18	2.2	2.56	2.82	2.69	0.7	2.46	3.54	3.45	2.2
	2.79	3.69	3.52	2.7	2.82	3.64	3.6	2.2	3.03	3.65	3.35	1.4	3	3.68	3.56	1.4	3	3.66	2.34	2.9	2.46	3.54	3.45	2.3	3.04	3.65	3.52	2.2
	3.54	3.6	2.48	2.6	3.35	3.71	3.61	2.4	3.47	2.18	2.84	1.7	3.38	3.71	3.61	1.4	2.93	3.71	3.61	2.5	3.09	3.69	3.55	2.1	3.49	3.5	3.44	3
	3.32	3.54	3.43	2.5	1.18	2.86	2.42	1.2	2.75	3.18	2.6	1.3	2.59	3.05	2.85	1.2	1.85	2.89	0.85	1.7	3.32	1.83	2.84	2.6	0.93	3.41	3.28	0.7
Jul	1.15	2.1	1.94	0.9	3	3.27	1.72	1.2	2.79	2.53	2.39	0.5	2.14	2.93	0.65	1	3.09	0.55	0.58	3.2	1.35	2.47	0.66	0.5	2.69	3.29	2.94	2.9
	2.94	3.03	2.87	1.5	2.88	3.41	3.17	0.8	2.32	3.04	2.2	0.7	3.25	3.42	3.23	0.7	1.55	2.86	2.69	1	1.24	2.76	0.5	0.7	1.22	2.77	2.55	2.1
	2.96	3.26	3.08	1.4	3.35	3.44	1.51	1.4	2.28	3.15	1.15	0.5	2.7	3.47	1.21	0.6	3.58	3.55	2.8	1.9	2.98	3.4	1.02	2	3.31	3.51	3.04	1.2
	3.33	3.37	1.62	1.8	3.31	3.52	3.29	1.5	2.66	3.28	2.32	0.6	2.2	3.35	1.19	0.5	2.27	3.41	2.43	1.9	2.84	3.46	3.28	1.2	2.36	3.37	2.57	2.6
Aug	2.47	3.39	0.5	1.9	2.58	3.39	0.52	1.2	2.13	3.41	1	1.1	3	3.5	1.05	0.6	3.19	3.39	0.5	3.2	3.24	3.67	1.21	2.2	2.35	3.39	0.5	2.3
	3.62	3.23	3.1	2.5	3.53	3.32	3.2	1.5	3.98	3.28	3.21	0.5	4.27	3.4	1.02	0.6	4.02	3.34	3	3.4	4.09	3.33	3.3	1.9	3.56	3.47	2.37	3.2
	4.21	3.45	0.6	4.5	3.95	3.43	2	1.6	4.26	2.7	3.67	1.8	4.12	3.08	-	0.9	3.6	3.14	2.26	3.3	4.31	3.37	3.15	1.9	3.38	3.18	1.81	3.6
	4.2	1.5	-	4.9	3.89	1.9	0.5	2.1	3.9	2.4	-	1	3.72	1.6	0.5	0.6	3.99	0.5	0.5	4.2	4.26	3.21	-	2.4	4.01	3.18	1.2	4.2
Sep	4.02	2.8	3.1	4	3.07	2.95	3	3.5	3.68	2.73	1	1.7	3.91	3.14	-	1.1	3.8	2	0.5	3.7	4.14	2.88	-	2.3	3.59	1.8	0.6	4
	3.12	2.97	-	3.8	3.02	3.06	0.7	1.7	3.34	3.22	-	2.3	2.81	3.29	-	0.5	3.7	2.6	0.6	3.6	3.09	3.12	2.8	3.1	3.43	1.5	1	3.6
	4.27	3.44	3.7	4	3.98	3.75	1.2	1.7	4.11	3.44	3.7	1.6	3.42	1.2	0.7	0.6	3.3	1.5	1	3.2	4.07	3.36	3.7	2.2	3.35	3.12	0.8	3.7
	3.11	2.7	1.9	3.2	3.39	3.34	3.6	1.9	2.99	3.32	3.2	1.4	2.93	3.54	1.9	0.6	3.27	1.99	1.2	3.3	3.31	3.28	3.5	1.9	3.38	3.04	1.8	3
Minimum:	1.15	1.50	0.50	0.90	1.18	1.90	0.50	0.80	2.13	2.04	0.50	0.50	2.14	1.20	0.50	0.50	1.15	0.50	0.50	1.00	1.24	1.50	0.50	0.50	0.93	1.50	0.50	0.70
Averages:	3.32	3.25	3.03	3.07	3.22	3.36	2.99	2.39	3.25	3.20	2.90	1.54	3.27	3.40	2.90	1.36	3.17	3.00	2.60	3.18	3.31	3.18	3.04	2.44	3.12	3.26	2.86	3.04
Maximum:	4.27	3.94	3.84	4.90	3.98	3.94	3.87	3.70	4.26	3.94	3.85	2.80	4.27	4.04	4.20	2.40	4.02	3.93	3.87	4.20	4.31	3.85	3.94	3.60	4.01	3.99	3.96	4.20







Chlorine Residual Sample Site #2 Data









Chlorine Residual Sample Site #6 Data









Chlorine Residual Sample Site #11 Data









Chlorine Residual Sample Site #13 Data









Chlorine Residual Sample Site #14 Data









Chlorine Residual Sample Site #15 Data





Chlorine Residual Sample Site #23 Data





Appendix G
CIP Plan Priority Matrix



CIP Priority Matrix

Priority No.	Option Count	Demand Condition	Demand	Project Determination Source	Problem/Issue(s) Solved	Length (~ LF)	Option Description (including location)	Improvement Cost Estimate (Current)	Improvement Cost Estimate (1-yr Inflation)*	Improvement Cost Estimate (2-yr Inflation)*	Improvement Cost Estimate (3-yr Inflation)*	Improvement Cost Estimate (4-yr Inflation)*	Improvement Cost Estimate (5-yr Inflation)*	Project Type	Year Installed	Infrastructure Age	Existing Pipe Material	Leakage Issues	Failure to Meet Hydraulic Criteria	Timeframe [i.e. Now (2015), 5-yr, Buildout]	Consequence of Failure (CoF)	Likelihood of Failure (LoF)	Risk Factor (CoF x LoF)
1	19	Now (2015)	-	City Request	Experience significant leakage, pressure issues, and maintenance requests on this water line	1499	Replacing 8-in CI with 8-in PVC Water Main (Greenhaven Village Shopping Ctr at Intersection of Marsh Ln & Spring Valley Rd)	\$566,622	\$566,622	\$589,287	\$612,858	\$637,373	\$662,868	Capital	1970	45	CI	Yes	No	Now (2015)	3.04	2.60	7.90
2	18	Now (2015)	-	City Request	Experience significant leakage, pressure issues, and maintenance requests on this water line	583	Replacing 8-in DI with 8-in PVC Water Main (Prestonwood Place Shopping Ctr near Intersection of Beltline Rd & Montfort Dr)	\$264,449	\$264,449	\$275,027	\$286,028	\$297,469	\$309,368	Capital	1979	36	DI	Yes	No	Now (2015)	2.91	2.54	7.40
3	16	5-Yr (2020)	PHD - 5-yr	Steady State Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000') & Replacing Old CI w/ new PVC	4254	Upsizing 8-in CI to 10-in PVC Water Main (Running N to S from Beltline Rd to George H.W. Bush Elementary)	\$953,249	\$953,249	\$991,379	\$1,031,034	\$1,072,275	\$1,115,167	Capital	1965	50	CI	No	Normal	5-Yr (2020)	2.93	2.00	5.85
4	17	5-Yr (2020)	PHD - 5-yr	Steady State Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000') & Replacing Old CI w/ new PVC	1617	Replacing 8-in CI with 8-in PVC Water Main (Intersection of Beltway Dr & Beltline Rd - Beltway Office Park)	\$611,226	\$611,226	\$635,675	\$661,102	\$687,546	\$715,048	Capital	1973	42	CI	No	Normal	5-Yr (2020)	2.53	2.00	5.05
5	6	Now (2015)	MDD + FF - Existing	City Request	Exceeding Maximum Allowable Velocity (7 fps) @ 1000 gpm	1271	Upsizing 6-in CI to 8-in PVC Water Main (Lake Forest Drive)	\$461,039	\$461,039	\$479,481	\$498,660	\$518,606	\$539,350	Capital	1969	46	CI	Yes	Fire Flow	Now (2015)	1.60	3.10	4.96
6	10	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1000 gpm	1388	Upsizing 6-in Unk to 8-in PVC Water Main (Apartment Complex at NE Intersection of Addison Rd and Westgrove Dr)	\$516,264	\$516,264	\$536,915	\$558,391	\$580,727	\$603,956	Capital	Unk	Unk	Unk	No	Fire Flow	Now (2015)	1.95	2.22	4.33
7	24	Now (2015)	MDD-Existing - EPS - Peak Hour	EPS Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000')	116	Upsizing 16-in DI to 24-in RCCP (Intersection of Belt Line Rd and Quorum Dr)	\$292,290	\$292,290	\$303,982	\$316,141	\$328,786	\$341,938	Capital	1983	32	DI	No	Normal	Now (2015)	2.43	1.44	3.49
8	23	Now (2015)	MDD-Existing - EPS - Peak Hour	EPS Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000')	1144	Upsizing 16-in RCCP to 24-in RCCP (in Belt Line Rd between Addison Rd and Quorum Dr)	\$845,736	\$845,736	\$879,565	\$914,748	\$951,338	\$989,391	Capital	1979	36	PCCP	No	Normal	Now (2015)	2.43	1.26	3.06
9	3	Now (2015)	PHD - Existing	Steady State Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000')	101	Upsizing 8-in DI to 10-in PVC Water Main Near 36-in to 8-in Connection (SE Corner of Village on the Parkway)	\$69,569	\$69,569	\$72,352	\$75,246	\$78,256	\$81,386	Maintenance	1978	37	DI	No	Normal	Now (2015)	1.25	1.44	1.80
10	7	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1000 gpm	1829	Upsizing 6-in PVC to 8-in PVC Water Main (Shadwood Apartments - Sydney Dr & Marsh Ln)	\$551,418	\$551,418	\$573,475	\$596,414	\$620,270	\$645,081	Capital	1976	39	PVC	No	Fire Flow	Now (2015)	1.48	1.10	1.62
11	2	Now (2015)	PHD - Existing	Steady State Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000')	8	Upsizing Short Connection from 6-in to 8-in (North of Beltline on Quorum)	\$24,192	\$24,192	\$25,160	\$26,166	\$27,213	\$28,301	Maintenance	1983	32	DI	No	Normal	Now (2015)	0.98	1.64	1.60
12	21	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	28	Upsizing 8-in PVC to 12-in PVC Water Main (The Wellington Square - Southern Edge of Addison)	\$26,531	\$26,531	\$27,592	\$28,695	\$29,843	\$31,037	Maintenance	1980	35	PVC	No	Fire Flow	Now (2015)	1.43	1.10	1.57
13	14	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	144	Upsizing 8-in PVC to 10-in PVC Water Main (Quorum Office Building #2)	\$81,178	\$81,178	\$84,425	\$87,802	\$91,314	\$94,967	Maintenance	1979	36	PVC	No	Fire Flow	Now (2015)	0.83	1.60	1.32
14	11	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	168	Upsizing 8-in PVC to 12-in PVC Water Main (Excel Telecommunications Service Center to Addison Rd)	\$106,122	\$106,122	\$110,367	\$114,782	\$119,373	\$124,148	Maintenance	1996	19	PVC	No	Fire Flow	Now (2015)	0.98	1.20	1.17
15	9	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1000 gpm	48	Upsizing 6-in Unk to 8-in PVC Water Main (Glenn Curtiss Dr & Addison Rd)	\$43,546	\$43,546	\$45,288	\$47,099	\$48,983	\$50,943	Maintenance	Unk	Unk	Unk	No	Fire Flow	Now (2015)	0.48	2.42	1.15
16	20	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	35	Upsizing 8-in Unk to 10-in PVC Water Main (The Madison - 15851 Dallas North Parkway)	\$22,050	\$22,050	\$22,932	\$23,849	\$24,803	\$25,795	Maintenance	1984	31	Unk	No	Fire Flow	Now (2015)	0.60	1.82	1.09
17	13	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	30	Upsizing 6-in Unk to 8-in PVC Water Main (Quorum Office Building #2)	\$27,216	\$27,216	\$28,305	\$29,437	\$30,614	\$31,839	Maintenance	1983	32	PVC	No	Fire Flow	Now (2015)	0.80	1.30	1.04
18	8	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1000 gpm	947	New 6-in PVC Water Main Loop (Talisner Apartments - off of Vitruvian Pkwy)	\$429,559	\$429,559	\$446,741	\$464,611	\$483,195	\$502,523	Capital	N/A	N/A	N/A	No	Fire Flow	Now (2015)	1.98	0.50	0.99
19	15	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	73	Upsizing 8-in PVC to 10-in PVC Water Main (Lateral off of Quorum Dr)	\$50,282	\$50,282	\$52,293	\$54,385	\$56,560	\$58,823	Maintenance	1979	36	PVC	No	Fire Flow	Now (2015)	0.53	1.60	0.84
20	4	Now (2015)	PHD - Existing	Steady State Model Determined	Exceeding Maximum Allowable Head Loss (4'/1000')	23	Upsizing 12-in PVC to 16-in DI Water Main Connection Between 36-in & 12-in Main (South of Beltline on Quorum)	\$25,734	\$25,734	\$26,764	\$27,834	\$28,948	\$30,105	Maintenance	1985	30	PVC	No	Normal	Now (2015)	0.78	0.90	0.70
21	25	Now (2015)	MinDD-EPS-Water Age Analysis	WAA Model Determined	Exceeding Allowable Water Age	149	New 8-in PVC Water Main Loop (Excel Telecommunications Service Center to Addison Rd)	\$238,341	\$238,341	\$247,875	\$257,790	\$268,101	\$278,825	Capital	N/A	N/A	N/A	No	Water Age	Now (2015)	0.55	1.00	0.55
22	22	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	20	Upsizing 8-in PVC to 12-in PVC Water Main (Millennium Phase I - NW Intersection of Arapaho & DNT)	\$18,950	\$18,950	\$19,708	\$20,497	\$21,317	\$22,169	Maintenance	1999	16	PVC	No	Fire Flow	Now (2015)	0.75	0.70	0.53
23	26	Now (2015)	MinDD-EPS-Water Age Analysis	WAA Model Determined	Exceeding Allowable Water Age	93	New 8-in PVC Water Main Loop (FedEx Store - 4901 Airport Pkwy)	\$298,972	\$298,972	\$310,931	\$323,368	\$336,303	\$349,755	Capital	N/A	N/A	N/A	No	Water Age	Now (2015)	0.53	0.70	0.37
24	12	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1500 gpm	813	New 10-in PVC Water Main Loop (One Hanover Park Offices to Excel Pkwy along DNT)	\$341,460	\$341,460	\$355,118	\$369,323	\$384,096	\$399,460	Planning	N/A	N/A	N/A	No	Fire Flow	Now (2015)	0.48	0.70	0.33
25	5	Now (2015)	MDD + FF - Existing	Steady State Model Determined	Exceeding Maximum Allowable Velocity (7 fps) @ 1000 gpm	210	Upsizing 6-in PVC to 8-in PVC Water Line for Lateral (Off of Claire Chennault Street)	\$105,840	\$105,840	\$110,074	\$114,477	\$119,056	\$123,818	Maintenance	2010	5	PVC	No	Fire Flow	Now (2015)	0.25	1.00	0.25
26	1	5-Yr (2020)	-	City Request	Public Loop Around Privately Owned Apt. Complex	3300	New 12-in PVC Water Main Loop (Apt. Complex in NW Corner of Town)	\$821,486	\$821,486	\$854,345	\$888,519	\$924,060	\$961,022	Planning	N/A	N/A	N/A	No	No	5-Yr (2020)	0.85	0.20	0.17

Notes:
 *Assumed 4.0% Inflation in accord with average inflation rates for the Dallas-Fort Worth Market per Engineering Judgement.
 **It has been assumed that within the first year inflation will not affect the improvement costs.



Appendix H

Risk Based Analysis Calculations & Data



Risk-Based Analysis - CIP Evaluation

Priority	Consequence of Failure Rankings (CoF): x-axis	CIP Option:			1			2			3			4			5			6			7		
		Consequences	Weight	%	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score
1	Health/Environmental (Water Quality)	10	100%	2-4 Apt. Buildings	4	4	Hotel(s)	5	5	2-4' Large Commercial	3	3	2-4' Large Commercial	3	3	1-2 Industrial	1	1	10+ SF Houses	5	5	10+ SF Houses	5	5	
2	Hydrants out of Service or Hydraulically	10	100%	2	2	2	2	2	2	5+	5	5	2	2	0-1	1	1	2	2	2	2	2	5+		
3	Meters out of Service	8	80%	2	1	0.8	0-1	0	0	2	1	0.8	0-1	0	0	0-1	0	0	6+	5	4	0-1	0-1		
4	Loss of Business	8	80%	0-1	0	0	0-1	0	0	0-1	0	0	0-1	0	0	0-1	0	0	0-1	0	0	0-1	0-1		
5	How Often Maintenance is Required	7	70%	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
6	Re-Construction Timeline	4	40%	0-1	0	0	0-1	0	0	1-3	1	0.4	1-3	1	0.4	0-1	0	0	5-7	3	1.2	5-7	5-7		
7	Temporary Service Availability	6	60%	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	Yes		
8	Location of Failure	2	20%	No	0	0	Medium	4	0.8	Medium	4	0.8	Medium	4	0.8	No	0	0	Light-Medium	3	0.6	Light-Medium	Light-Medium		
				0.85			0.975			1.25			0.775			0.25			1.6			1.47			

Priority	Likelihood (Risks) of Failure Rankings - Failure Mode (LoF): y-axis	CIP Option:			1			2			3			4			5			6			7		
		Risks	Weight	%	Lookup Value	Rating	LoF Score																		
1	Age of Infrastructure	10	100%	N/A	0	0	32	3	3	37	3	3	30	2	2	5	0	0	46	4	4	39	3	3	
2	Pipe Material	9	90%	N/A	0	0	DI	3	2.7	DI	3	2.7	PVC	0	0	PVC	0	0	CI	5	4.5	PVC	5	4.5	
3	Known Leakage Issues	9	90%	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	Yes	5	4.5	No	5	4.5	
4	Hydraulic Criteria	5	50%	No	0	0	Normal	3	1.5	Normal	3	1.5	Normal	3	1.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	
5	Looping Redundancy	5	50%	2	2	1	2	2	1	3+	0	0	2	2	1	1	5	2.5	3+	0	0	3+	3+		
				0.2			1.64			1.44			0.9			1			3.1			1.1			

Likelihood is weighted on a 1-10 Scale; the closer it is to 10 the more important it is.

Likelihood (Risks) of Failure Rankings - Failure Mode (LoF) - Lookup Table

Weight	Age of Infrastructure		Pipe Material		Known Leakage Issues		Hydraulic Criteria		Looping Redundancy	
	Age	Rating	Material	Rating	Yes/No	Rating	Failure to Meet	Rating	Redundancy Routes	Rating
	0-10	0	CI	5	Yes	5	Fire Flow	5	1	5
	10-20	1	Unk	4	No	0	Water Age	5	2	2
	20-30	2	DI	3			Normal	3	3+	0
	30-40	3	PCCP	2			No	0		
	40-50	4	Steel	1						
	50+	5	PVC	0						

Consequence is weighted on a 1-10 Scale; the closer it is to 10 the more important it is.

Consequences of Failure Rankings (CoF) - Lookup Table

Weight	Health/Environmental (Water Quality)		Hydrants out of Service or Hydraulically Hindered		Meters out of Service		Loss of Business		How Often Maintenance is Required		Re-Construction Timeline		Temporary Service Availability		Location of Failure	
	Criteria (No. of Affected)	Rating	Criteria (Number)	Rating	Yes/No	Rating	Criteria (Number)	Rating	Criteria (No. per year)	Rating	Criteria (No. of Months)	Rating	Yes/No	Rating	Trafficked	Rating
	0-5 SF Houses	3	0-1	1	0-1	0	0-1	0	0	0	0-1	0	Yes	0	N/A	0
	5-10 SF Houses	4	2	2	2	1	2	2	1	1-3	1	No	5	No	0	
	10+ SF Houses	5	3-5	4	3	2	3	4	2	3	3-5	2		Lightly	2	
	0-5 Small Commercial	3	5+	5	4	3	4+	5	3+	5	5-7	3		Light-Medium	3	
	5-10 Small Commercial	4			5	4					7-9	4		Medium	4	
	10+ Small Commercial	5			6+	5					9+	5		Heavily	5	
	1-2 Apt. Buildings	3														
	2-4 Apt. Buildings	4														
	4+ Apt. Buildings	5														
	1-2 Large Commercial	2														
	2-4 Large Commercial	3														
	4+ Large Commercial	5														
	1-2 Industrial	1														
	2-4 Industrial	2														
	4+ Industrial	4														
	School(s)	5														
	Hospital(s)	5														
	Hotel(s)	5														
	N/A	0														



Risk-Based Analysis - CIP Evaluation

		8		9		10		11		12		13		14		15		16		17												
Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating											
5	5	10+ SF Houses	5	5	1-2 Industrial	1	1	4+ Apt. Buildings	5	5	1-2 Large Commerical	2	2	1-2 Large Commerical	2	2	2-4' Large Commerical	3	3	2-4' Large Commerical	3	3	1-2 Large Commerical	2	2	School(s)	5	5	4+ Large Commercial	5	5	
5	5	5+	5	5	2	2	2	5+	5	5	5+	5	5	0-1	1	1	0-1	1	1	0-1	1	1	0-1	1	1	5+	5	5	5+	5	5	
0	0	6+	5	4	0-1	0	0	6+	5	4	0-1	0	0	2	1	0.8	0-1	0	0	0-1	0	0	0-1	0	0	6+	5	4	6+	5	5	
0	0	0-1	0	0	0-1	0	0	0-1	0	0	0-1	0	0	2	2	1.6	2	2	1.6	0-1	0	0	0-1	0	0	4+	5	4	4+	5	5	
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3	1.2	5-7	3	1.2	1-3	1	0.4	5-7	3	1.2	1-3	1	0.4	0-1	0	0	1-3	1	0.4	1-3	1	0.4	1-3	1	0.4	9+	5	2	7-9	4	4	
0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	No	5	3	Yes	0	0	
3	0.6	Light-Medium	3	0.6	Lightly	2	0.4	Lightly	2	0.4	Lightly	2	0.4	No	0	0	Light-Medium	3	0.6	Light-Medium	3	0.6	Medium	4	0.8	Lightly	2	0.4	Light-Medium	3	0.6	
*5		1.975		0.475		1.95		0.975		0.475		0.8		0.825		0.525		2.925		2.525												
Rating	LoF Score	Lookup Value	Rating	LoF Score	Lookup Value	Rating	LoF Score	Lookup Value	Rating	LoF Score	Lookup Value	Rating	LoF Score	Lookup Value	Rating	LoF Score	Lookup Value	Rating	LoF Score	Lookup Value	Rating											
3	3	N/A	0	0	Unk	5	5	Unk	5	5	19	1	1	N/A	0	0	32	3	3	36	3	3	36	3	3	50	4	4	42	4	4	
0	0	N/A	0	0	Unk	4	3.6	Unk	4	3.6	PVC	0	0	N/A	0	0	PVC	0	0	PVC	0	0	PVC	0	0	CI	5	4.5	CI	5	5	
0	0	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	No	0	0	
5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Normal	3	1.5	Normal	3	3	
0	0	3+	0	0	2	2	1	3+	0	0	1	5	2.5	2	2	1	2	2	1	1	5	2.5	1	5	2.5	3+	0	0	3+	0	0	
		0.5		2.42		2.22		1.2		0.7		1.3		1.6		1.6		2		2												



Risk-Based Analysis - CIP Evaluation

18				19				20				21				22				23				24				25				26			
CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score	Lookup Value	Rating	CoF Score					
5	5-10 Small Commercial	4	4	5-10 Small Commercial	4	4	1-2 Large Commercial	2	2	2-4 Large Commercial	3	3	1-2 Large Commercial	2	2	4+ Large Commercial	5	5	4+ Large Commercial	5	5	1-2 Large Commercial	2	2	1-2 Large Commercial	2	2	1-2 Large Commercial	2	2					
5	3-5	4	4	5+	5	5	2	2	2	3-5	4	4	2	2	2	5+	5	5	5+	5	5	0-1	1	1	0-1	1	1	0-1	1	1					
4	5	4	3.2	5	4	3.2	0-1	0	0	3	2	1.6	2	1	0.8	5	4	3.2	5	4	3.2	0-1	0	0	0-1	0	0	0-1	0	0					
4	4+	5	4	4+	5	4	0-1	0	0	2	2	1.6	0-1	0	0	4+	5	4	4+	5	4	0-1	0	0	0-1	0	0	0-1	0	0					
0	3+	5	3.5	3+	5	3.5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0					
1.6	5-7	3	1.2	5-7	3	1.2	1-3	1	0.4	3-5	2	0.8	3-5	2	0.8	5-7	3	1.2	5-7	3	1.2	3-5	2	0.8	3-5	2	0.8	3-5	2	0.8					
0	No	5	3	No	5	3	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0	Yes	0	0					
0.6	Lightly	2	0.4	Lightly	2	0.4	Lightly	2	0.4	Lightly	2	0.4	Lightly	2	0.4	Heavily	5	1	Heavily	5	1	Light-Medium	3	0.6	Lightly	2	0.4	Lightly	2	0.4					
2.9125				3.0375				0.6				1.425				0.75				2.425				2.425				0.55				0.525			

18				19				20				21				22				23				24				25				26			
LoF Score	Lookup Value	Rating	LoF Score																																
4	36	3	3	45	4	4	31	3	3	35	3	3	16	1	1	36	3	3	32	3	3	N/A	0	0	N/A	0	0	N/A	0	0					
4.5	DI	3	2.7	CI	5	4.5	Unk	4	3.6	PVC	0	0	PVC	0	0	PCCP	2	1.8	DI	3	2.7	N/A	0	0	N/A	0	0	N/A	0	0					
0	Yes	5	4.5	Yes	5	4.5	No	0	0																										
1.5	No	0	0	No	0	0	Fire Flow	5	2.5	Fire Flow	5	2.5	Fire Flow	5	2.5	Normal	3	1.5	Normal	3	1.5	Water Age	5	2.5	Water Age	5	2.5	Water Age	5	2.5					
0	1	5	2.5	3+	0	0	3+	0	0	3+	0	0	3+	0	0	3+	0	0	3+	0	0	3+	0	0	1	5	2.5	2	2	1					
2.54				2.6				1.82				1.1				0.7				1.26				1.44				1				0.7			



Appendix I Proposed Impact Fee Schedule



DEVELOPMENT FEE SCHEDULE

TYPE OF SUBMITTAL	REVIEW FEE
Zoning Change	0 – 0.99 Acres..... \$250
Planned Development	1.00 – 4.99 Acres..... \$450
	≥ 5.00 Acres..... \$750
Special Use Permit	\$650
Zoning Variance Request	\$50
Preliminary Plat Final Plat Replat / Amended Plat Plat Vacation	\$300 each
Concept Plan	\$300 + \$25/Acre*
Preliminary Site Plan	\$300 + \$25/Acre*
Site Plan	0 – 4.99 Acre..... \$350 + \$50/Acre*
	≥ 5.00 Acre..... \$500 + \$50/Acre*
Building Elevations / Façade Plan	\$150
Landscape Plan	0 – 4.99 Acres..... \$150 + \$50/Acre*
	≥ 5.00 Acres..... \$250 + \$50/Acre*
Civil Engineering Plans / Construction Set	\$500 + \$25/Acre*
	Initial Review Fee Covers 1 st – 3 rd submittal; Each additional submittal (4 th +): \$500 + \$100/Acre*
Traffic Impact Analysis (without modeling)	\$1000
Traffic Impact Analysis (with modeling)	\$1500

*Calculate as per acre or portion thereof.



UTILITY FEE SCHEDULE

ITEM	FEE
Utility Verification Letter	\$50
Sanitary Sewer Connection (based on connection size)	4 Inch..... \$100
	6 Inch..... \$150
	8 Inch..... \$200
Domestic Water Connection (based on meter size)	0.75 Inch..... \$300
	1 Inch..... \$400
	1.5 Inch..... \$850
	2 Inch..... \$900
	3 Inch..... \$1500
	4 Inch..... \$2000
	6 Inch..... \$4000
	8 Inch..... \$5000
10 Inch..... \$6000	
12 Inch..... \$8000	
Irrigation Water Connection (based on meter size)	Same as domestic meter connection fees
Construction Water Meter	\$1500 deposit + \$1/day + \$2.37/1000gal usage
Public Works Inspection	4% of public infrastructure cost + hourly overtime cost (if applicable)
Contractor Registration Fee	\$100



MISCELLANEOUS PERMIT FEE SCHEDULE

TYPE OF PERMIT	FEE
Right of Way	\$50
Fence	Single Family Residential: \$25 Commercial / Multi-Family: \$100
Demolition	\$100
Sign	\$100



Appendix J
Impact Fee Analysis Calculations & Data



Water, Sewer, and Irrigation Impact Fees for Various Cities

Utility Fee Schedule		Impact Fee Comparison																						
Item	Size/Description	Addison		Plano				McKinney			Carrollton		Grand Prairie				Allen		Little Elm		Arlington			
		Simple (Positive Displ.)	Turbine	Amount	Electronic Meter Reader	Total Simple (PD)	Turbine	Simple	Compound	Turbine	Simple (Positive Displ.)	Turbine	North Sector - Simple (PD)	North Sector - Turbine	South Sector - Simple (PD)	South Sector - Turbine	Simple	Compound	Simple (Positive Displ.)	Turbine	Residential - Simple (PD)	Residential - Turbine	Commercial - Simple (PD)	Commercial - Turbine
Utility Verification Letter	-	\$50																						
Sanitary Sewer Connection (based on connection size)	5/8 inch												\$190		\$543		\$1,258	\$500						\$2,492
	3/4 inch							\$174					\$270		\$815		\$1,887	\$750					\$380	\$670
	1 inch							\$290					\$440		\$1,358		\$3,145	\$1,250					\$6,645	\$1,173
	1.5 inch							\$580					\$840		\$2,715		\$6,290	\$2,500					\$8,307	\$2,680
	2 inch							\$928	\$928	\$1,856			\$1,330		\$4,344		\$10,064						\$2,660	\$4,690
	3 inch								\$1,856	\$4,061					\$8,688		\$20,128		\$4,000				\$6,080	\$10,720
	4 inch		\$100	\$50			\$50		\$2,900	\$7,541				\$5,220		\$13,575		\$31,450		\$8,000		\$12,500	\$33,227	\$18,760
	6 inch		\$150	\$75			\$75		\$5,801	\$16,242				\$11,560		\$27,150		\$62,900		\$25,000		\$40,000	\$83,067	\$42,880
	8 inch		\$200	\$125			\$125		\$9,281	\$27,844				\$13,440		\$43,440		\$100,640		\$40,000		\$60,000	\$38,000	\$67,000
	10 inch									\$40,606				\$30,890		\$62,445		\$144,670		\$57,500			\$57,000	\$100,500
	12 inch									\$51,048														
	Domestic Water Connection (based on meter size)*	5/8 inch												\$750		\$1,711		\$3,617		\$1,200			\$1,578	
3/4 inch		\$300		\$163	\$145	\$308		\$1,418					\$1,050		\$2,567		\$5,425		\$1,800			\$480		\$845
1 inch		\$400		\$222	\$145	\$367		\$2,364					\$1,750		\$4,278		\$9,042		\$3,000			\$840		\$1,479
1.5 inch		\$850		\$396	\$145	\$541		\$4,727					\$3,300		\$8,555		\$18,085		\$6,000			\$1,920		\$3,380
2 inch			\$900	\$520	\$145		\$665	\$7,564						\$5,250		\$13,688		\$28,936		\$9,600		\$10,517	\$3,360	\$5,915
3 inch			\$1,500	\$2,725	\$350		\$3,075	\$15,127							\$27,376		\$57,872		\$19,200			\$7,680		\$13,520
4 inch			\$2,000	\$3,612	\$350		\$3,962	\$23,636						\$20,600		\$42,775		\$90,425		\$30,000		\$21,035	\$13,440	\$23,660
6 inch			\$4,000	\$7,040	\$350		\$7,390	\$47,272						\$45,600		\$85,550		\$180,850		\$60,000		\$52,587	\$30,720	\$54,080
8 inch			\$5,000	\$6,426	\$350		\$6,776	\$75,635						\$53,000		\$136,880		\$289,360		\$96,000		\$48,000	\$48,000	\$84,500
10 inch			\$6,000	\$10,534	\$350		\$10,884			\$330,90				\$121,850		\$196,765		\$415,955		\$138,000		\$72,000	\$72,000	\$126,750
12 inch			\$8,000				\$0			\$451,99														
Irrigation Water Connection (based on meter size)*		5/8 inch																		\$1,200				
	3/4 inch		\$300	\$163	\$145	\$308													\$1,800			\$480		\$845
	1 inch		\$400	\$222	\$145	\$367													\$3,000			\$840		\$1,479
	1.5 inch		\$850	\$396	\$145	\$541													\$6,000			\$1,920		\$3,380
	2 inch		\$900	\$788	\$145		\$933	\$15,127												\$9,600			\$3,360	\$5,915
	3 inch		\$1,500	\$1,496	\$145		\$1,641	\$33,091												\$19,200			\$7,680	\$13,520
	4 inch		\$2,000	\$2,238	\$145		\$2,383	\$61,454												\$30,000			\$13,440	\$23,660
	6 inch		\$4,000	\$3,978	\$145		\$4,123	\$132,36												\$60,000			\$30,720	\$54,080
	8 inch		\$5,000	\$6,426	\$145		\$6,571	\$226,90												\$96,000			\$48,000	\$84,500
	10 inch		\$6,000	\$10,534	\$145		\$10,679													\$138,000			\$72,000	\$126,750
	12 inch		\$8,000				\$0																	
	Construction Water Meter	-	\$1500 deposit + \$1/day + \$2.37/1000gal usage																					
Public Works Inspection	-	4% of public infrastructure cost + hourly overtime cost (if applicable)											4% inspection fee for all work performed in the City ROW or Easement											4% total project cost (\$330 minimum)
Contractor Registration Fee	-	\$100				\$100																		



Water, Sewer, and Irrigation Impact Fees for Various Cities (Continued)

Utility Fee Schedule		Impact Fee Comparison																							
Item	Size/Description	Fees																							
		Prosper			Mesquite			Eules		Midlothian		Garland		The Colony			Frisco		Rockwall			Fort Worth			
		Displacement	Compound	Turbine	Positive Displ.	Compound	Turbine	Simple (Positive Displ.)	Turbine	Simple (Positive Displ.)	Turbine			Simple	Compound	Turbine	Positive Displ. - SF Land Use	Positive Displ. - Other Use	Compound	Turbine	Simple	Compound	Turbine	Simple (Positive Displ.)	Turbine
Utility Verification Letter	-																								
Sanitary Sewer Connection (based on connection size)	5/8 Inch	\$273			\$919					\$525	\$2,771			\$815			\$1,619				\$1,236				\$452
	3/4 Inch				\$1,379					\$525				\$1,223											\$678
	1 Inch	\$683			\$2,298					\$1,312	\$3,879			\$2,038			\$1,619	\$3,885			\$3,091				\$1,129
	1.5 Inch	\$1,366		\$2,186	\$4,595					\$2,624				\$4,075			\$8,094				\$12,950	\$6,181			\$2,258
	2 Inch	\$2,186		\$2,732	\$7,352	\$7,352	\$14,704			\$4,198		\$11,084			\$6,520	\$8,150	\$12,950				\$16,188	\$9,890	\$9,890	\$19,781	\$3,612
	3 Inch		\$6,147	\$6,147		\$16,083	\$32,165			\$12,593		\$38,794			\$13,040	\$19,560			\$25,901	\$38,851		\$19,781	\$43,270		\$9,820
	4 Inch		\$13,660	\$16,392		\$27,570	\$59,735			\$22,037		\$66,504			\$20,375	\$34,230			\$40,470	\$67,990		\$30,907	\$80,359		\$16,932
	6 Inch		\$27,320	\$34,150		\$62,033	\$128,660			\$48,272		\$138,550			\$40,750	\$74,980			\$80,940	\$148,930		\$61,814	\$173,080		\$36,120
	8 Inch			\$54,640		\$82,710	\$220,560			\$83,952		\$199,512			\$65,200	\$130,400						\$98,903	\$296,709		\$63,210
	10 Inch			\$88,790			\$321,650					\$321,436					\$203,750								\$94,815
12 Inch																									
Domestic Water Connection (based on meter size)*	5/8 Inch	\$1,560			\$1,721			\$1,478		\$1,880		\$25		\$1,653			\$1,772				\$1,556				\$469
	3/4 Inch				\$2,582			\$1,478				\$28		\$2,480											\$704
	1 Inch	\$3,900			\$4,303			\$3,695		\$2,632		\$35		\$4,133			\$1,772	\$4,430			\$3,889				\$1,173
	1.5 Inch	\$7,800		\$12,480	\$8,605			\$7,390				\$45		\$8,265			\$8,859				\$14,174	\$7,778			\$2,345
	2 Inch	\$12,480		\$15,600	\$13,768	\$13,768	\$27,536			\$11,823	\$7,520	\$73		\$13,224	\$16,530	\$14,174				\$17,718	\$12,444	\$12,444	\$24,888		\$3,752
	3 Inch		\$35,100	\$35,100		\$30,118	\$60,235			\$35,470	\$26,320	\$275		\$26,448	\$39,672			\$28,349	\$42,523		\$24,888	\$54,443			\$10,201
	4 Inch		\$78,000	\$93,600		\$51,630	\$111,865			\$62,072	\$45,120	\$350		\$41,325	\$69,426			\$44,295	\$74,416		\$38,888	\$101,109			\$17,588
	6 Inch		\$156,000	\$195,000		\$116,168	\$240,940			\$135,967	\$94,000	\$525		\$82,650	\$152,076			\$88,590	\$163,006		\$77,776	\$217,774			\$37,520
	8 Inch			\$312,000		\$154,890	\$413,040			\$236,464	\$135,360	\$725		\$132,240	\$264,480						\$124,442	\$373,326			\$65,660
	10 Inch			\$507,000			\$602,350				\$218,080					\$413,250									\$98,490
12 Inch																									
Irrigation Water Connection (based on meter size)*	5/8 Inch																								\$469
	3/4 Inch																								\$704
	1 Inch																								\$1,173
	1.5 Inch																								\$2,345
	2 Inch															\$16,530							\$24,888		\$3,752
	3 Inch															\$39,672							\$54,443		\$10,201
	4 Inch															\$69,426							\$101,109		\$17,588
	6 Inch															\$152,076							\$217,774		\$37,520
	8 Inch															\$264,480							\$373,326		\$65,660
	10 Inch															\$413,250									\$98,490
12 Inch																									
Construction Water Meter	-																								
Public Works Inspection	-																								
Contractor Registration Fee	-																								





Water Meter Impact Fees for Various Cities

		Addison	Plano	McKinney	Carrollton	Grand Prairie - North Sector	Grand Prairie - South Sector	Allen	Little Elm	Arlington - Residential	Arlington - Commercial	Prosper	Mesquite	Euless	Midlothian	Garland	The Colony	Frisco - SF Land-Use	Frisco - Other Use	Rockwall	Fort Worth	
Domestic Water Connection (based on meter size)	Simple (Positive Displ.)	5/8 Inch	\$0	\$0	\$750	\$1,711	\$3,617	\$1,200	\$1,578	\$0	\$0	\$1,560	\$1,721	\$1,478	\$1,880	\$25	\$1,653	\$1,772	\$0	\$1,556	\$469	
		3/4 Inch	\$300	\$308	\$1,418	\$1,050	\$2,567	\$5,425	\$1,800	\$0	\$480	\$845	\$0	\$2,582	\$1,478	\$0	\$28	\$2,480	\$0	\$0	\$0	\$704
		1 Inch	\$400	\$367	\$2,364	\$1,750	\$4,278	\$9,042	\$3,000	\$4,207	\$840	\$1,479	\$3,900	\$4,303	\$3,695	\$2,632	\$35	\$4,133	\$1,772	\$4,430	\$3,889	\$1,173
		1.5 Inch	\$850	\$541	\$4,727	\$3,300	\$8,555	\$18,085	\$6,000	\$5,259	\$1,920	\$3,380	\$7,800	\$8,605	\$7,390	\$0	\$45	\$8,265	\$8,859	\$0	\$7,778	\$2,345
	Turbine/Compound	2 Inch	\$900	\$665	\$7,564	\$5,250	\$13,688	\$28,936	\$9,600	\$10,517	\$3,360	\$5,915	\$15,600	\$27,536	\$11,823	\$7,520	\$73	\$16,530	\$17,718	\$0	\$24,888	\$3,752
		3 Inch	\$1,500	\$3,075	\$15,127	\$0	\$27,376	\$57,872	\$19,200	\$0	\$7,680	\$13,520	\$35,100	\$60,235	\$35,470	\$26,320	\$275	\$39,672	\$42,523	\$0	\$54,443	\$10,201
		4 Inch	\$2,000	\$3,962	\$23,636	\$20,600	\$42,775	\$90,425	\$30,000	\$21,035	\$13,440	\$23,660	\$93,600	\$111,865	\$62,072	\$45,120	\$350	\$69,426	\$74,416	\$0	\$101,109	\$17,588
		6 Inch	\$4,000	\$7,390	\$47,272	\$45,600	\$85,550	\$180,850	\$60,000	\$52,587	\$30,720	\$54,080	\$195,000	\$240,940	\$135,967	\$94,000	\$525	\$152,076	\$163,006	\$0	\$217,774	\$37,520
		8 Inch	\$5,000	\$6,776	\$75,635	\$53,000	\$136,880	\$289,360	\$96,000	\$0	\$48,000	\$84,500	\$312,000	\$413,040	\$236,464	\$135,360	\$725	\$264,480	\$0	\$0	\$373,326	\$65,660
		10 Inch	\$6,000	\$10,884	\$330,905	\$121,850	\$196,765	\$415,955	\$138,000	\$0	\$72,000	\$126,750	\$507,000	\$602,350	\$0	\$218,080	\$0	\$413,250	\$0	\$0	\$0	\$98,490
12 Inch	\$8,000	\$0	\$451,995	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	





Water Impact Fee Comparison by Meter Size







Water Impact Fee Comparison by Meter Size







Water Impact Fee Comparison by Meter Size







Water Impact Fee Comparison by Meter Size






Water Impact Fee Comparison by Meter Size





Water Impact Fee Comparison by Meter Size







Note:

Out of the cities considered in the impact fee analysis, McKinney is the only one to have an impact fee listed for 12-inch water meters.




Minimum, Maximum, and Average Water Impact Fees by Meter Size





Minimum, Maximum, and Average Water Impact Fees by Meter Size



Note:
Out of the cities considered in the impact fee analysis, McKinney is the only one to have an impact fee listed for 12-inch water meters.